


Company- CREST DRILLING COMPANY, et al
Farm- Wheeler No. 1

SEC. 5 T. 27 R. 23
SE SE SE

Total Depth. 3415
Comm. 5-29-52 Comp. 6-11-52
Shot or Treated.
Contractor. Crest Drilling Co.
Issued. 7-19-52

County Sedgwick
KANSAS



CASING:

8 5/8" 86' cem w/75 sx

Elevation. 1393 D.F.

1395 (handwritten)

Production. dry

Figures indicate Bottom of Formations.

surface soil	45
lime	50
lime, shale	80
sand water	84
lime	86
lime, shale	415
lime	585
shale, lime	1680
lime, sandy shale	1915
lime, shale	2350
lime, sandy shale	2415
shale	2475
shale & K.C. lime	2555
lime, shale	2635
lime	2670
shale	2820
shale, lime	2955
lime, Miss.	3182
lime, shale	3285
lime-Viola	3310
sand - Viola	3347
sand Simpson, shale	3395
shale, lime	3415
Total Depth	

Tops:

Mississippi Lime	2950
Viola Lime	3291
Simpson Sand	3311
Arbuckle Lime	3398

All measurements from rotary
bushing 2 1/2' above derrick
floor.