

15-173-03803-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


2-27-2E

Company- H. H. BLAIR
Farm- Krug No. 1

SEC. 2 T. 27 R. 2E
SW SW SE

Total Depth. 3314'
Comm. 1-31-61 Comp. 2-15-61
Shot or Treated.
Contractor. Red Drig. Co.
Issued. 4-1-61

County Sedgwick
KANSAS



Elevation. 1374' RB

Production. Dry

CASING:
8 5/8" 166' cem w/150 sx.

Figures indicate Bottom of Formations.

clay & shale	76
shale - lime shls	90
lime & shale	480
shale & lime shls	530
shale & lime	630
lime & shale	645
shale & lime shls	860
shale - shells	1225
sandy shale	1300
shale - lime shls	1485
shale & lime strks	2075
lime & shale	2215
shale	2230
lime	2289
shale & lime	2440
lime	2586
shale	2625
shale - lime shls	2795
shale & lime	2835
shale - lime shls	2878
chert & lime	2895
lime	3134
shale & lime	3153
shale	3180
lime	3214
sand	3235
sand & shale	3272
Core #1	3302
lime	3314
Total Depth	
TOPS: SCOUT	
Lansing	2063
Kansas City	2431
Mississippi	2885
Kinderhook	3137
Viola	3185
Simpson Sand	3212
Lower Simpson Sand	3289
Arbuckle Dolomite	3302