

MAGNOLIA PETRO.CO.
A. Jabs No. 1.

SEC. 8 T. 27 R. 2E
NE NW SE

Total Depth. 3310'
Comm. 8-25-38 Comp. 9-28-38
Shot or Treated.
Contractor.
Issued. 11-19-38

County. Sedgwick



CASING:
13" 116'
8 5/8" 2969'
7" 3254'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

lime & shale	250
lime	508
shale & lime shells	545
lime	845
lime & shale	1085
shale	1242
lime & shale	1325
shale	1425
lime	1495
shale & lime	1765
lime	1818
shale	1828
lime	1980
lime & shells	2012
shale & lime	2105
shale & shells	2132
lime	2152
shale	2186
lime hrd	2220
lime sft	2318
lime hrd	2343
lime	2383
shale hrd	2423
shale & shells	2500
Top Kansas City lime	2500
Kansas City lime	2672
Kansas City lime sft	2570-85
Kansas City lime firm	2585-90
Kansas City lime hrd	2610-33
lime & shale	2680
shale	2727
lime	2745
shale	2755
lime	2785
shale red	2790
lime	2824
lime & shale	2957
shale Top Chat	2967
chat	2970
Standardized	
shale blue	2984
dry from	2969-2984
chat white hrd	2984
chat	3060
lime hrd	3076
lime	3174
shale green	3180
shale green	3197
lime	3225
shale blk	3235
shale (Top Misener sand	3279
Misener sand	3279) 3280
Misener dolomite	3300
Top Viola dolomite	3300
Viola dolomite	3310
Total Depth.	

1000' salt wtr & 0 oil 2984-86
Dry hole 3254-3282
Picked up approx. 200' of wtr at 3282
Firm Misener sand - no oil - water
gradually increased and at 3310
hole approx. full of water.
Plugged & Abnd.