

115341

15-015-19773-00-00

15-27-3E

Doc Source: KS Geol. Surv.
Page 1 of 1


KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY ~~E. V.~~ H. V. ELWELL

SEC. 15 T. 27 R. 3E
LOC. NE NE SW

FARM Elwell NO. 1

TOTAL DEPTH 3217
COMM. 1-19-51 COMP. 2-6-51
SHOT OR TREATED
CONTRACTOR
ISSUED 3-10-51



CASING

8 5/8" 104' cem w/ 85 sx
10 3/4" 389' cem w/105 sx

ELEVATION 1348 D.F.

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

soil, sand 108
sand, shale 215
shale sandy 227
sand 235
sand-Drilled with-
out circulation..250

Skidded Rig

surface hole 120
sand, shale 195
lime cherty 289
lime cherty, shale 400
lime, shale 724
shale 910
lime 940
shale, lime 1650
lime 1705
lime, shale 1900
shale, sand 2035
lime 2090
lime, shale 2335
lime 2401
lime, shale 2456
lime 2545
shale 2638
lime, shale 2824
lime 2833
lime, shale, chert 2900
lime, chert 2908
lime 3074
shale, lime, chert 3077
shale 3102
shale, sand 3107
sand 3133
shale sandy 3150
shale, sand 3193
lime 3217 RTD
Total Depth

Tops:
Topeka 1390
Heebner 1764
Toronto 1776
Base Oread 1801
Stalnaker Sand 2003
Lansing 2036
Kansas City 2334
Base Kansas City 2535
Mississippi Lime 2850
Base Miss. Lime 3033
Simpson Sand 3104
Arbuckle 3185