

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Exxon Mobil Oil Corporation
Address: PO Box 4358 Houston TX 77210
Phone: 713 431 1936 Operator License #: 5208
Type of Well: Gas Docket #:
The plugging proposal was approved on: 2-14-08
by: Ken Jehlik
Is ACO-1 filed?
Producing Formation(s): Chase Depth to Top: 2550 Bottom: 2669 T.D. 2680

API Number: 15-189-00180-00-00
Lease Name: Lowe A
Well Number: 1
Spot Location (QQQQ): C-NE
1260 Feet from North / South Section Line
1260 Feet from East / West Section Line
Sec. 25 Twp. 31 S. R. 35 East West
County: Stevens
Date Well Completed: 12-29-54
Plugging Commenced: 2-14-08
Plugging Completed: 2-14-08

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes entries for 10 3/4, 7, and 5 1/2 liner casings.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Top of junk @ 1903. Ran 2 3/8 to 1900. Pumped 70 bbls. mud to circ. hole. Mixed 100 lb. hulls + 40 sx cmt. plug from 1900 to 1700. Pull to 1100. Mixed 200 lb. hulls @ leak. Pull to 580. Mixed 40 sx 580 to 380. Pull to 40. 8 sx plug 40 to 0. 7 was cmt.d to surface. Cut off 10 3/4 + 7 + capped 10 3/4 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: EXXON MOBIL
State of KANSAS County, STEVENS, ss.

RICHARD B LEWIS (Employee of Operator) or (Operator) on above-described well, sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC, State of Kansas DORETTA L. DELAY My Appt. Exp. 12-27-08

(Signature) RB Lewis (Address) 200 W 4th HUGOTON KS 67951

Permitting Doretta L. Delay My Commission Expires 12-27-08

FEB 26 2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

regulatory contact: Jacqueline Davis 281-654-1913 2/29/08

RECEIVED KANSAS CORPORATION COMMISSION

MAR 03 2008

CONSERVATION DIVISION WICHITA, KANSAS

Handwritten signature/initials