

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 15 Twp. 28 Rge. 2 (E) E (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner John P. Gaty  
Lease Name Wehrman "B" Well No. 1  
Office Address 4201 E. Douglas, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed September 27, 1960  
Application for plugging filed September 27, 1960  
Application for plugging approved September 27, 1960  
Plugging commenced September 27, 1960  
Plugging completed September 27, 1960  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3384 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	139	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 180'  
Set plug, 1/4 sack hulls  
20 sacks cement on top plug  
Heavy mud to 35'  
Set plug, 1/4 sack hulls  
10 sacks cement on top plug to surface

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1960  
9-29-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beaumont Petroleum Company  
Address P.O. Box 1276, El Dorado, Kansas


STATE OF KANSAS, COUNTY OF BUTLER, ss.  
H. F. Filson (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. F. Filson  
El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of September, 19 60

My commission expires 3-21-64

Notary Public.



GATY - #1 Bessie Wehrman "3"

Contracted - Beaumont Petroleum Company

Rot. T.D. 3384  
 Conn. Rot. 9-19-60  
 Comp. Rot. 9-27-60

Cemented  
 8 5/8 Surface w/100 ex  
 Halliburton Company

Casing Record  
 8 5/8 139

Elev: 1358 K.S.

FIGURES INDICATE BOTTOM OF FORMATIONS  
 ROTARY BURNING 5' ABOVE GROUND LEVEL

cellar	5
soil	20
lime-shale	100
shale-lime	140
lime-sdy lime-shale	410
shale-lime	1275
shale-lime-shells	1555
shale-lime strks	1845
shale-lime	2040
edy lime-shale-sand	2110
shale	2125
lime-shale strks	2330
shale-lime	2520
K.C. lime	2630
shale-lime	2945
shale	2972
Miss. lime	3240
shale	3300
shale with lime	3342
Simpson sand	3384 Rot. T.D.

Formations:

T. K.C. ls	2511
B. K.C. ls	2719
T. Miss. ls	2972
B. Miss. ls	3238
T. Kind. sh	3238
Basal Miss. ls	3266
T. Kind. sh.	3292
T. Simpson sh	3342
T. Simpson ss	3346
Rot. T.D.	3384

September 27, 1960  
 D & A Plugged and abandoned