

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sedgwick SEC. 7 TWP. 26 RGE. 2 E/W
Location as in quarters or footage from lines:
NE SW SE

Lease Owner Griggs Oil, Inc.
 Lease Name Stannard Well No. #1
 Office Address 1625 Vickers KSB&T Bldg. Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole.
 Date Well Completed 1-28-82
 Application for plugging filed 1-28-82
 Plugging commenced 1-28-82
 Plugging completed 1-28-82
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3480'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	240'	NONE


Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.
Mud to 248', 30 sx. cement.
Mud to 60', Cemented to 0'.
5 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) *Ernest Sifford*
401 E. Douglas #500 Wichita,
 (Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1982



Carolyn J. Tjaden
 Carolyn J. Tjaden - Notary Public.

My Commission expires: _____

RECEIVED
 STATE CORPORATION COMMISSION
2-4-82
FEB - 4 1982
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS LOG

OPERATOR: Griggs Oil, Inc. 1625 Vickers KSB&T Bldg. Wichita, Kansas 67202

CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042**

Lease Name Stannard Well No. #1

Sec. 7 T. 26 R. 2E Spot NE SW SE

County Sedgwick State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 240' with _____ Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 3480'

Drilling Commenced: 1-19-82 Drilling Completed 1-28-82

Formation	From	To	Tops	
Cellar	0	7	Kansas City	2530
Shale	7	745	Burgess	3008
Shale, Lime	745	1725	Mississippi	3118
Lime, Shale	1725	1943		
Shale, Lime	1943	2360		
Lime, Shale	2360	2475		
Shale	2475	2530		
Lime	2530	2712		
Shale, Lime	2712	2749		
Lime, Shale	2749	2975		
Shale, Lime	2975	3008		
Sand	3008	3118		
Lime	3118	3236		
Lime, Shale	3236	3440		
Sand	3440	3480		

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log

Type and Depths Covered **RECEIVED**
STATE CORPORATION COMMISSION

FEB - 4 1982

CONSERVATION DIVISION
Wichita, Kansas