

15-173-00464-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Sedgwick County. Sec. 7 Twp. 26S Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Charles Lamer Carlock

Lease Name Schramm Well No. 1

Office Address 102 Insurance Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 8, 1955 19

Application for plugging filed March 21, 1955 19

Application for plugging approved March 21, 1955 19

Plugging commenced March 24, 1955 19

Plugging completed March 28, 1955 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 2968 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 97     | None       |
|           |         |      |    | 5-1/2" | 2964'  | ?          |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled bottom of hole with sand to 2950 feet. Dumped 6 sacks of cement at 2950 feet. Mudded hole to 90 feet. Hole made solid at 90 feet and dumped 15 sacks of cement at 90 feet. Mudded hole to 20 feet; set bridge and 5 sacks of cement at top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Company

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Charles L. Carlock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles Lamer Carlock

102 Insurance Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of April, 1955

My commission expires July 25, 1956.



Lorraine Polaw Notary Public.

PLUGGING FILE SEC 7 T26 R2E BOOK PAGE 05 LINE 34

RECEIVED STATE CORP. COM. DIVISION APR 8 1955 4-8-55 CONSERVATION DIVISION

DRILLING LOG

Company: Chas L. Carlock  
102 Insurance Bldg.,  
Wichita, Kansas

Lease: Schramm

Well: #1

Location NE NE SE of Section 7, Township 26, Range 2 East,  
Sedgwick County, Kansas

Contractor: Bedell-Catt Drilling Co., Inc.  
623 Union Nat'l Bank Bldg.  
Wichita 2, Kansas

Date Comm: February 28, 1955

Date Compl: March 8, 1955

T.D. 2964'

Production:

Casing: 8 5/8" to 97'  
5 1/2" to 2964'

Figures Indicate the Bottom of Formation

|      |                     |
|------|---------------------|
| 0-40 | Sod & shale         |
| 97   | Shale & lime shells |
| 555  | Shale & lime        |
| 670  | Lime & shale stks   |
| 2475 | Shale & lime        |
| 2678 | Lime                |
| 2964 | Shale & lime - T.D. |

I certify the above to be true and correct to the best  
of my knowledge and belief.

BEDELL-CATT DRILLING CO., INC.

By *Carl Bedell*

Subscribed and sworn before me this 10th day of March,

1955.

*Frances L. Wilber*  
Notary Public

My Commission Expires

*March 18, 1958*

