

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County, Sec. 12 Twp. 28 Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Mack Oil Company

Lease Name Lowery Well No. 1

Office Address 812 Union Center Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-16 19 63

Application for plugging filed 9-16 19 63

Application for plugging approved 9-16 19 63


Plugging commenced 9-16 19 63

Plugging completed 9-16 19 63

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Paul Turpin

Producing formation None Depth to top Bottom Total Depth of Well 3270' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 210 feet. Set a dry hole plug and added 1/2 sack hulls, added 15 sacks cement. Mudded hole to 25' of surface. Set plug, added 1/4 sack hulls and 8 sacks cement. Capped rat hole with 2 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1963
9-24-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mack Oil Company
Address Box 400, Duncan, Oklahoma

STATE OF Kansas COUNTY OF Sedgwick ss.
Robert L. Harris (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Harris

812 Union Center Bldg., Wichita, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 63

Ronald L. Iron

Notary Public.



MACK OIL COMPANY
Duncan, Oklahoma



DRILLERS WELL LOG

Lowery #1

Commenced R.D.: 9-9-63
Completed R.D.: 9-16-63
Total Depth: 3270'

SW SW SW Sec. 12-28S-2E
Sedgwick County, Kansas
Elevation: 1363 K.B.
Initial Production: D & A
Contractor: Mack Oil Company

<u>STRATA</u>	<u>DEPTH</u>
Sand, Shale & Lime	0 - 628
Sand & Shale	628 - 881
Shale, Sand & Lime	881 - 2290
Shale & Lime	2290 - 2961
Lime	2961 - 3019
Shale & Lime	3019 - 3186
Shale, Sand & Lime	3186 - 3270

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1963

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Robert L. Harris

Signed and sworn to in my presence this 23rd day of September, 1963, by Robert L. Harris, representative of Mack Oil Company.

Ronald L. Irion
Ronald L. Irion
Notary Public

My commission expires: 2-7-66

