


15-015-00619-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Butler County. Sec. 25 Twp. 27 Rge. 3(E) (W)
Location as "NE/CNW&SW" or footage from lines NE NE NW
Lease Owner E. H. Adair Oil Co.
Lease Name Lygrisse Well No. 1
Office Address 1005 E. 2nd. Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 2-9-56 19
Application for plugging filed 2-18-59 19
Application for plugging approved 2-23-59 19
Plugging commenced 2-26-59 19
Plugging completed 2-26-59 19
Reason for abandonment of well or producing formation Oil Exhausted

If a producing well is abandoned, date of last production May 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation Simpson Depth to top 2989 Bottom 2993 Total Depth of Well 2993 Feet
Show depth and thickness of all water, oil and gas formations. 3001 AUG 28

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Drillers Log attached hereto.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bridge at 180 feet, used 15 feet of rock and 15 sacks of cement. Mud to 40 feet, used ten sacks of cement to top of the hole.

RECEIVED
STATE CORPORATION COMMISSION
3/13/59
MAR 13 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Co.
Address 1005 E. Second Wichita

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Sherrill Compton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sherrill Compton
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1959

My commission expires 9-15-61 L. Hill Notary Public.

PLUGGING
FILE SEC 25 T. 27 R. 3E
BOOK PAGE 16 LINE 19

E. H. Adair Oil Company
Wichita 7, Kansas.

E. H. Adair Oil Company
Lygrisse No. 1
NE NE NW of
Sec. 25-Twp. 27S.-Range 3 E.
Butler County, Kansas.

Elev.: 1324 K.B.

Comm.: 1-9-56
Comp.: 1-19-56
Contractor:
Adair - Rig No. 2.
8-5/8 @ 165 ft. w/190 ex.
5-1/2 @ 2989 ft. w/50 ex.

Pro. _____

Figures indicate bottoms of Formations

Line	to	355	Shale & lime	to	2552
Line & shale		1800	Line		2562
Sand		1830	Shale & lime		2592
Shale		1927	Line		2602
Line		1948	Line & shale		2625
Colitic lime		1984	Black shale		2627
Lime		1980	Line & shale		2648
Line & shale		2024	Black shale		2651
Line		2028	Line & shale		2670
Shale		2088	Shale		2689
Line		2098	Line & shale		2704
Shale & lime		2116	Shale		2712
Shale		2274	Line		2721
Line		2280	Shale		2725
Black shale		2281	Black shale		2726
Shale		2334	Line & shale		2735
Shale		2335	Black shale		2737
Line		2368	Line & shale		2756
Line		2406	Chert		2760
Shale		2414	Line		2743
Line		2417	Shale		2746
Shale		2421	Line		2761
Shale & lime		2430	Shale		2765
Shale		2435	Line		2778
Line		2442	Shale & lime		2883
Shale		2446	Line		2915
Shale & lime		2469	Shale		2940
Shale		2500	Shale & siltstone		2958
Line & shale		2522	Shale		2989
Shale		2534	Sand		2993

DST #1: 1948-55. Open one hour. Shut in 20 minutes. Weak blow throughout. Recovered 18 feet drilling-mud. BHP = 720 lbs.

DST #2: 2987-93. Open 35 minutes. Shut in 20 minutes. Weak blow for 18 minutes. Recovered 5 feet mud. BHP = 710 lbs.

Geological Tops

LANSING	1927	(-603)
KANSAS CITY	2274	(-950)
MISSISSIPPI	2756	(-1432)
KINDERHOOK	2915	(-1591)
SIMPSON	2989	(-1665)
R.T.D	2993.	

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1959
CONSERVATION DIVISION
Wichita, Kansas

Certified correct:

Sherrill Compton
Sherrill Compton, Geologist.

PLUGGING		
FILE	SEC. 25	T. 27, R. 3E
BOOK	PAGE 16	LINE 19