


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County, Sec. 25 Twp. 27 Rge. 3 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW - NW - NE
Lease Owner Brooks Pierce Drilling Company
Lease Name Ingold Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 12 - 26 19 56
Plugging completed _____ 12 - 30 19 56
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence Matthews
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	165	None
				5 1/2	3016	2615.56

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded from 3058 to 3000 - dumped 3 sks cement - pulled pipe - mudded hole to 165' - set 15' rock bridge - dumped 15 sks cement - mudded to 20' - set rock bridge - dumped 5 sks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License 236
Address Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Brooks Pierce

~~employee of owner~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Brooks Pierce
1014 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 19 57

My commission expires September 8, 1958.

Louise K. Bowman Notary Public.

24-7366-S 3-53-20M

PLUGGING
FILE SEC 25 T. 27 R. 3E
BOOK PAGE 129 LI E. 26

RECEIVED
JAN 30 1957
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

DRILLING LOG

Company: Brooks Pierce Drilling Company
1013 Union Center
Wichita, Kansas

Lease: Ingold

Well: #1

Location: NW NW NE of Section 25, Township 27, Range 3 East,
Butler County, Kansas

Contractor: Bedell-Catt Drilling Co., Inc.
605 Union Nat'l Bank Bldg.,
Wichita 2, Kansas

Date Comm: July 14, 1956

Date Compl: July 27, 1956

T. D. 3025'

Productions:

Casings: 8 5/8" to 163' w/ 250 sx cement
5 sx C.C.
5 1/2" to 3025'

Figures Indicate the Bottom of Formation

0-163	Surface hole	2664'	Lime & shale
226	Lime & shale	2761'	Shale & lime
245	Lime & shale stks	2821	Miss Chert & Lime
264	Lime	2911	Cherty lime
274	Shale	2928	Miss lime
340	Shale & lime stks	3008	Shale
420	Lime	3025	Simpson Sand -
475	Lime & shale		Top 3007'
32 - 132'	Plug & cement		
1770	Shale & lime	3025'	T.D.
1900	Shale & lime stks		
1933	Shale & lime		
2245	Lansing lime Top - 1933'		
2370	Lime		
2492	K.C. Lime Top - 2285'		

I certify the above to be true and correct to the best of my knowledge and belief.

BEDELL-CATT DRILLING CO., ETC.

By Corb S. Bedell
Corb S. Bedell

PLUGGING
FILE S 25 27
BOOK PAGE 749 LINE 28

Subscribed and sworn before me this 31st day of July, 1956.

L. Dehler
Notary Public

My Commission Expires:

March 18, 1958