

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Comp 6-3-34

LEASE NAME BOLITHO

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 24 TWP. 27 SRGE. 3 (E) or (X)

COUNTY Butler

Date Well Completed 6-3-34

Plugging Commenced 8/5/97

Plugging Completed 8/7/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR AZTEC OIL COMPANY

ADDRESS P.O. Box 1020, El Dorado, Ks 67042

PHONE#() OPERATORS LICENSE NO. 5387

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Aug 7, 1997 (date)

by Jerry Clark - State plugger (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3011'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				6 5/8"	2812'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SEE BACK OF PAGE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dale Wilson d/b/a W. W. Drilling License No. 6012

Address 3603 NE 4th St. El Dorado, Kansas 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Aztec Oil Co.

STATE OF Kansas COUNTY OF Butler, ss.


Dale Wilson, plugging contractor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) 3603 NE 4TH ST.

El Dorado, Ks, 67042

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 97



Emma K. Utermoehlen
Notary Public

My Commission Expires:

Plugging report Form CP-4

AZTEC OIL COMPANY
P.O. Box 1020
El Dorado, Kansas 67042

LEASE: BQLITHO WELL # 1
Butler County, Kansas

Strung tools to 2800' Plug back with gravel to 2750'. Mix & dump 10 sacks @ 2750'. Put rock bridge from 300' to 260'. Had cellar & pit dug. Run 1" pipe to 250' on outside of 8 5/8" csg. United spotted 30 sacks ~~60-40 pozmix cement + 2% gel & 2% CC @ 250'. Pull 1" pipe.~~

Run 1" pipe to 250'. No fillup on cement. United spotted 50 sacks 60-40 pozmix cmt + 2% gel & 4% CC @ 250'. Pulled 1" pipe & let cement set 2½ hours. Run 1" pipe to 220', top of cement. Spotted 165 sacks 60-40 pozmix cmt + 2% gel & 4% CC @ 220'. Run 2 3/8" tubing to 140', top of cmt. Spotted 100 sacks 60-40 pozmix + 2% gel + 4% CC & 300 # hulls @ 140'. Run 2 3/8" tubing to 140', top of cement. Spotted 100 sacks 60-40 pozmix + 2% gel, 4% CC & 400 # hulls @ 140'. Pull tubing.

Run 2 3/8" tubing to 105', top of cement. United spotted 75 sacks 60-40 pozmix cmt + 2% gel, 4% CC & 250# hulls. Pull tubing. Run tubing to 65'. Circulate 115 sacks 60-40 pozmix cmt + 2% gel & 2% CC from 65' to surface. Put 71 sacks 60-40 pozmix + 2% gel & 2% CC inside of 7" csg from 260' to surface. Used total 635 sacks 60-40 pozmix cement on outside of 8 5/8". Used 71 sacks 60-40 pozmix inside of 7" csg.

