

15-015-22089-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION Rev. 12-15-80
8/12/82
AUG 12 1982

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Butler SEC. 24 TWP. 27 RGE. 3E E/W
Location as in quarters or footage from lines:
50' SW of NE SW NW

Lease Owner R. R. Abderhalden
Lease Name Stelbar Well No. 1
Office Address 510 Hardage Center - Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 7/31/82
Application for plugging filed Yes
Plugging commenced 7/31/82
Plugging completed 7/31/82
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation _____ Depth to top _____ bottom _____ T.D. 3010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole from 3010' T.D. to 240' with drilling mud, added 35 sx. cement,

filled with drilling mud to 60', added 20 sx. cement. 10 sx. cement in rathole.

10 sx. cement in mousehole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. R. A., Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

R. R. Abderhalden (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature)

R. R. Abderhalden
510 Hardage Center - Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 82



My Commission expires

Ada C. May
Ada C. May Notary Public.

DRILLER'S LOG

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1982

CONSERVATION DIVISION
Wichita, Kansas

R. R. Abderhalden
Stelbar No. 1
50' SW of NE SW NW
Sec. 24-T27S-R3E
Butler County, Kansas

Commenced: 7/23/82
Completed: 7/29/82

Surface Casing: 216' of 8-5/8"
Cemented w/ 200 sx., 3% CC

<u>Formation</u>	<u>Depth</u>
Surface	0 - 227
Lime, Shale, & Red Bed	227 - 467
Shale	467 - 867
Shale w/ lime streaks	867 - 1360
Lime w/ shale	1360 - 1660
Shale	1660 - 1920
Lime & Shale	1920 - 2254
Kansas City	2254 - 2442
Shale & Lime	2442 - 2600
Shale	2600 - 2748
Lime	2748 - 3010 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

R. R. Abderhalden

R. R. Abderhalden

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 11th day of August 1982.



Ada C. May
Notary Public Ada C. May