

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County, Sec 4 Twp. 27S Rge. 3 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW

Lease Owner Petroleum Management, Inc.

Lease Name Holliday A. Owen Holliday Well No. 1

Office Address 1019 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.

Date well completed 1-4 1957

Application for plugging filed 1-9 1957

Application for plugging approved 1-10 1957

Plugging commenced 2-2 1957

Plugging completed 2-4 1957

Reason for abandonment of well or producing formation Dry hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Lawrence W. Matthews

Producing formation Simpson Depth to top 3000' Bottom 3065' Total Depth of Well 3033' PB Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Simpson	Oil and water.	3001'	3021'	8 5/8"	203'	None.
				4 1/2"	3064'	2594'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3 sacks cement on bottom and mud to 216'. Set 10' rock bridge and topped with 10 sacks cement to 206'. Left surface pipe intact to be used in testing for fresh water.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Top Drilling Company

Address Winfield, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

John W. Ritchey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John W. Ritchey*

c/o Petroleum Management, Inc., 1019 Central Bldg. Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 18th day of March, 1957

My commission expires April 23, 1958

Notary Public.

STATE CORPORATION COMMISSION
3/20/57
MAR 20 1957

PLUGGING
FILE SEC. 24 T. 27 R. 3E
BOOK PAGE 132 LINE 31

CONSERVATION DIVISION
Wichita, Kansas

PRAIRIE OIL & GAS COMPANY, INC.
 308 PETROLEUM BUILDING
 WICHITA 2, KANSAS

 L 0 0

HOLIDAY NO. 1

NE 1/4, SEC. 24-27S-3E,
 BUTLER COUNTY, KANSAS
 LOCATION: NE SE NW

OWNER: PETROLEUM MANAGEMENT, INC. AND
 PRAIRIE OIL & GAS CO., INC.
 CONTRACTOR: PRAIRIE OIL & GAS CO., INC.

DRILLING COMMENCED 12/12/56
 DRILLING COMPLETED 12/20/56

ELEVATIONS: 1336' OF

8-5/8" OD 203' CEMENTED W/115 SACKS
 4 1/2" OD 3065' CEMENTED W/75 SACKS

SURFACE CLAY	10
BROKEN LIME	345
SHALE & SHELLS	1900
LANSING SHALE & LIME	1925
LIME	1985
SHALE	2234
K.C. LIME	2363
LIME	2500
SHALE	2775
MISS. LIME	2952
SHALE	2997
SHALE - CORED	3000
SIMPSON SAND - CORED	3015
SIMPSON SAND	3027
SHALE	3065 RTD.

STATE CORPORATION COMMISSION

MAR 2 1957

STATE CORPORATION COMMISSION

PLUGGING
 FILE SEC. 24 T. 27 R. 3E
 BOOK PAGE 132 LINE 31