

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 015 - 00830 - 00 - 0 (of this well)

Operator's Full Name RAINS + WILLIAMSON Oil Co. Inc.

Complete Address 435 Page Cte, 220 W. Douglas Wichita, KS 67202

Lease Name Myler Unit ^{KCC} _{2AP} Well No. # 1

Location App SW-SW-SE Sec 21 Twp 27S Rge. 3 (E)

County Butler Total Depth 3075'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor RAINS + WILLIAMSON Oil Co. Inc.

Address SAME AS ABOVE License No. 682

Operation Completed: Hour 3:20 P.M. Day 16 Month 1 Year 1980

The above well was plugged as follows:

8 5/8" sur. csg. 198' - circ/cemt. 4 1/2" csg. 3074'
Pulled 19 joints, app. 608', tried to run new csg. could not.
Pulled 608' csg. left, 2466' csg. in hole.
Closed well in with 8 5/8" to 2" sledge + 2" stop.
United Cementing + Acid Co. Inc. pumped 3 sx gel, 2 sx bulk,
100 sx cement down 8 5/8" csg. Pump Press 150 #
S. I. P. 50 # left csg. full cement.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
1/18/80
JAN 18 1980

Signed: Don Thompson
Well Plugging Supervisor

INVOICED

DATE 1-18-80

INV. NO. 6983-E

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,
 Wichita, Kansas

COPY


15-015-00830-00-00

Company. SHAWVER-ARMOUR, INC.
 Farm. Myler Unit No. 1

SEC. 21 T. 27 R. 3E
 SW SW SE

Total Depth. 3076'
 Comm. 6-22-61 Comp. 6-30-61
 Shot or Treated.
 Contractor. Shawver-Armour, Inc.
 Issued. 9-16-61

County Butler
 KANSAS



CASING:
 8 5/8" 198' cem w/175 sx.
 4" 3070'

Elevation. 1327' KB

Production. 17 BOPD

Figures Indicate Bottom of Formations.

| | |
|------------------|----------|
| lime & shale | 645 |
| shale & lime | 2135 |
| Kansas City | 2353 |
| Kansas City lime | 2405 |
| lime | 2481 |
| Kansas City lime | 2525 |
| lime & shale | 2555 |
| shale & lime | 2635 |
| lime & shale | 2766 |
| shale & lime | 2785 |
| Mississippian | 2885 |
| lime | 3007 |
| shale & lime | 3015 |
| shale | 3065 |
| Core #1 | 3076 RTD |
| Total Depth | |

| | |
|------------------|------|
| TOPS: | |
| Kansas City | 2324 |
| Base Kansas City | 2516 |
| Mississippian | 2785 |
| Kinderhook | 3006 |
| Simpson | 3070 |

RECEIVED
 STATE CORPORATION COMMISSION

DEC 26 1979

CONSERVATION DIVISION
 Wichita, Kansas