

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

MAR 13 2008

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

WELL PLUGGING RECORD
K.A.R. 82-3-117

CONSERVATION DIVISION
WICHITA, KS

Lease Operator: EOG Resources, Inc.
Address: 3817 NW Expressway, Suite 500 Oklahoma City, OK 73112-1483
Phone: (405) 246-3100 Operator License #: 5278

API Number: 15-189-22599-00-00
Lease Name: Central Plains 27
Well Number: # 1

Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): SW - SW - NE - SW
1550 Feet from North / South Section Line
1550 Feet from East / West Section Line

The plugging proposal was approved on: 2/24/2007 12/27/07 (Date)
by: Lynn Reimer (KCC District Agent's Name)

Sec. 27 Twp. 33 S. R. 39 East West
County: Stevens

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Lower Morrow Depth to Top: 6114' Bottom: 6156' T.D. 6600'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Date Well Completed: 7/17/2007
Plugging Commenced: 2/26/2008
Plugging Completed: 2/27/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lower Morrow	Dry	Surface	6595'	4 1/2"	6595'	3472'
		Surface	1559'	8 5/8"	1559'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH w/ tbg, load csg w/mud & set 4 1/2" CIBP @ 6064', cap w/ 2 sks cement in one bailer run. Cut & pull 4 1/2" csg from 3472'. TIH w/ tbg at 1620' & spot 80 sks cement up to 1360'. Pull up hole w/ tbg @ 575' & spot 50 sks cement up to 410', Top out 34' - 4' with 10 sks cement.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706 Duncan, OK 73534

Name of Party Responsible for Plugging Fees: EOG Resources Inc.

State of OK County, OK, ss.

Bev Christensen (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 3817 NW Exp., Suite 500 Oklahoma City OK 73112
SUBSCRIBED and SWORN TO before me this 11th day of March 2008
[Signature] My Commission Expires: 6/30/09
Notary Public 01010621

[Handwritten initials]