

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.
Address: P.O. Box 352, Russell, KS 67665
Phone: (785) 483-3145, Ext. 214 Operator License #: 5135
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: District #4 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing "C" Depth to Top: 3542' Bottom: 3548' T.D. 3811'
Arbuckle Depth to Top: 3807' Bottom: 3811' T.D. 3811'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-01,358-00-00
Lease Name: Swenson "B"
Well Number: #3
Spot Location (QQQQ): _____ - NW - NW - SW
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 8 Twp. 9 S. R. 21 East West
County: Graham
Date Well Completed: 2-19-54 12/29/54
Plugging Commenced: 3-4-08
Plugging Completed: 1:30 P.M., 3-4-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing "C"	oil & water	3542'	3548'	8-5/8"	153'	-0-
Arbuckle	oil & water	3807'	3811'	5-1/2"	3807'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Prior to plugging the casing was perforated: 2 holes @ 1825' & 2 holes @ 1050'. Ran 2-7/8" tubing to 3600' - spotted 250# hulls w/ 40 sks. cement on bottom & 15 sks. gel above cement. Pulled up to 1850' & circulated cement to surface w/130 sks. cement & 750# hulls. Pulled tubing & squeezed 20 sks. cement @ 400 PSIG down casing & shut in. 8-5/8" backside - mixed 5 sks. cement @ 400 PSIG & shut in.

TOTAL: 195 sks. 60/40 Pozmix, 15 sks. 4% gel, 1000# hulls

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 3152
Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.

State of Kansas County, Russell, ss.


John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 12th day of March, 20 08

Margaret A. Schulte
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC PKT per RBDS

RECEIVED
MAR 13 2008
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]

ALLIED CEMENTING CO., LLC. 30180

COPY

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell KS

DATE <u>3-4-08</u>	SEC. <u>8</u>	TWP. <u>9</u>	RANGE <u>21W</u>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>1:30pm</u>
LEASE <u>Swenson "B"</u>	WELL # <u>3</u>	LOCATION <u>Palco KS Redline West to</u>			COUNTY <u>Graham</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>Bogue Rd 3 1/4 N East into</u>				

CONTRACTOR Poe Servicing Inc.
 TYPE OF JOB Plug Old Well
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE 2 7/8 DEPTH 3600'
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER John Roberts
 # 409 HELPER Adrian
 BULK TRUCK _____
 # 362 DRIVER Travis
 BULK TRUCK _____
 # 396 DRIVER Chris B.

REMARKS:

Run 2 7/8 Tubing To 3600' spot 250# Hulls with 40 sks cement on bottom + 15 sks gel above cement Pulled up to 1850' and circulated cement to surface w/ 130 sks cement and 700# Hulls. Pulled tubing and squeezed 20sk cement @ 400psi down casing and shut in. 8 3/8 backside mixed 5sk @ 400 psi and shut in

CHARGE TO: John O Farmer
 STREET _____
 CITY _____ STATE _____ ZIP _____

OWNER (Used 195 sks cement - 15 sks gel 1000# Hull)

CEMENT AMOUNT ORDERED 325 6 1/4 4% Gel
18 sks Gel on side
1000# Hulls on side

COMMON	<u>117</u>	@ <u>12.15</u>	<u>1421.55</u>
POZMIX	<u>78</u>	@ <u>6.80</u>	<u>530.40</u>
GEL	<u>22</u>	@ <u>18.25</u>	<u>401.50</u>
CHLORIDE		@	
ASC		@	
<u>Hulls 10</u>		@ <u>27.95</u>	<u>279.50</u>
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>357</u>	@ <u>2.05</u>	<u>731.85</u>
MILEAGE	<u>SK/M/09</u>		<u>1606.50</u>
			<u>4971.30</u>

TOTAL

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>789.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>50</u>	@ <u>7.00</u>	<u>350.00</u>
MANIFOLD	@		
	@		
	@		

TOTAL 1139.00

PLUG & FLOAT EQUIPMENT

 @ _____
 @ _____
 @ _____
 @ _____
 @ _____

RECEIVED
 KANSAS CORPORATION COMMISSION
MAR 13 2008
 CONSERVATION DIVISION
 WICHITA, KS

TOTAL _____

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.
 Thanks!

PRINTED NAME _____
 SIGNATURE Dwain H. Eckman

Perf-Tech

Wireline Services, Inc.

Invoice

P.O. Box 87
 HAYS, KS 67601-0087
 (785) 623-3969

DATE	INVOICE #
3/5/2008	5480

Marger


COPY

BILL TO
John O. Farmer 370 W. Wichita Avenue P.O. Box 352 Russell, KS 67665

RECEIVED MAR 10 2008

SERVICE DATE	DESCRIPTION	ITEM	AMOUNT
3/4/2008	Swenson B #3 B #7 Graham County Kansas		
	Well B #3 Perforated to plug well 2 holes at 1825' 2 holes at 1050'	PERF	900.00T
	Well B #7 Perforated to plug well 2 holes at 1840' 2 holes at 1050'	PERF	900.00T
	Sales Tax		99.90

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAR 13 2008
 CONSERVATION DIVISION
 WICHITA, KS

Thank you for your business. 	Total	\$1,899.90
--	--------------	------------