

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.
Address: P.O. Box 352, Russell, KS 67665
Phone: (785) 483-3145, Ext. 214 Operator License #: 5135
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: District #4 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing "C" Depth to Top: 3564' Bottom: 3568' T.D. 3700'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-20,043 -00-00
Lease Name: Swenson "B"
Well Number: #7
Spot Location (QQQQ): _____ - W/2 - NE - SW
1980 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 8 Twp. 9 S. R. 21 East West
County: Graham
Date Well Completed: 7-6-67
Plugging Commenced: 3-4-08
Plugging Completed: 7:00 P.M., 3-4-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansng "C"	oil & water	3564'	3568'	8-5/8"	164'	-0-
				5-1/2"	3721'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Prior to plugging the casing was perforated: 2 holes @ 1840' & 2 holes @ 1050'. Ran 2-7/8" tubing to 3600' - mixed 100 sks. cement w/500# hulls. Pulled up to 2600' - mixed 75 sks. cement w/100# hulls. Pulled up to 1875' - mixed 150 sks. cement w/200# hulls to circulate to surface. Pulled tubing out of hole & mixed 40 sks. cement down casing - shut in @ 200 PSIG. Mixed 10 sks. cement down 8-5/8" backside & shut in.


TOTAL: 375 sks. 60/40 Pozmix, 800# hulls.

Name of Plugging Contractor: poeservicing inc License #: 3152 RECEIVED
Allied Cementing Company, Inc. KANSAS CORPORATION COMMISSION
Address: P.O. Box 31, Russell, KS 67665 KEEPER PER MAR 13 2008
Name of Party Responsible for Plugging Fees: John O. Farmer, Inc. CP2/3 CONSERVATION DIVISION
State of Kansas County, Russell, ss. WICHITA, KS

John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer III
(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 12th day of March 20 08
Margaret A. Schulte My Commission Expires: _____
Notary Public



BARNETT OIL COMPANY
SWENSON "B" NO. 7
A/C W/2 NE/4 SW/4 SECTION 8-9S-21W
GRAHAM COUNTY, KANSAS

COPY

DRILLER'S LOG

<u>From</u>	<u>To</u>	<u>Formation</u>
0	20	Surface Clay
20	40	Sand
40	55	Shale
55	85	Sand
85	290	Shale
290	1040	Shale and Shells
1040	1215	Shale and Sand
1215	1525	Shale and Shells
1525	1557	Sand and Shale
1557	1785	Shale and Red Bed
1785	1809	Shale and Shells
1809	1844	Anhydrite
1844	2055	Shale and Shells
2055	2595	Lime and Shale
2595	2700	Lime
2700	3035	Lime and Shale
3035	3355	Lime
3355	3415	Lime and Shale
3415	3855	Lime (T.D.)

Set 8 5/8", 24# @ 164'
w/150 sacks

Set 5 1/2", 15.50# @ 3721'
w/125 sacks

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 13 2008

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., LLC

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell KS

COPY

DATE <u>3-4-08</u>	SEC. <u>8</u>	TWP. <u>9</u>	RANGE <u>21 W</u>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>7:00 pm</u>
LEASE <u>Swenson B</u>	WELL # <u>7</u>	LOCATION <u>Palca KS Redline West to</u>			COUNTY <u>Graham</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD <input type="radio"/> NEW (Circle one)			Bogue Rd 3 1/4 N East into				

CONTRACTOR Poe Servicing Inc.

TYPE OF JOB Plug old well

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 7/8 DEPTH 3600'

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER (Used 375 sks cement 800# Hulls)

CEMENT AMOUNT ORDERED 460 60/40 4% Gel
800# Hulls on side

COMMON	<u>225</u>	@ <u>12.15</u>	<u>2733.75</u>
POZMIX	<u>150</u>	@ <u>6.80</u>	<u>1020.00</u>
GEL	<u>13</u>	@ <u>18.25</u>	<u>237.25</u>
CHLORIDE		@	
ASC		@	
Hulls	<u>8</u>	@ <u>27.25</u>	<u>218.00</u>
		@	
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>481</u>	@ <u>2.05</u>	<u>986.05</u>
MILEAGE	<u>SK/m/07</u>		<u>8164.50</u>
TOTAL			<u>7365.15</u>

EQUIPMENT

PUMP TRUCK CEMENTER John Roberts

409 HELPER Adrian

BULK TRUCK DRIVER Travis

362

BULK TRUCK DRIVER Chris B

396

REMARKS:

Run 2 7/8 tubing to 3600' mixed 100sk cement with 500# hulls. Pulled up to 2600' mix 75sks w/ 100# Hulls. Pulled up to 1875' mix 150sks w/ 200# Hulls to circulate to surface. Pulled tubing out of hole and mixed 40 sks down casing shut in 200ps. Mixed 10 sks down 8 3/8" back side and shut in.

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE	<u>2nd well</u>		<u>400.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>50</u>	@ <u>7.00</u>	<u>350.00</u>
MANIFOLD		@	
		@	
TOTAL			<u>400.00</u>

CHARGE TO: John O Farmer

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 13 2008

CONSERVATION DIVISION
WICHITA, KS

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE Duane Edman

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

Perf-Tech

Wireline Services, Inc.

P.O. Box 87
HAYS, KS 67601-0087
(785) 623-3969

Invoice

DATE	INVOICE #
3/5/2008	5480

Marger

COPY

BILL TO
John O Farmer 370 W. Wichita Avenue P.O. Box 352 Russell, KS 67665

RECEIVED MAR 10 2008

SERVICE DATE	DESCRIPTION	ITEM	AMOUNT
3/4/2008	Swenson B #3 B#7 Graham County Kansas		
	Well B#3 Perforated to plug well 2 holes at 1825' 2 holes at 1050'	PERF	900.00T
	Well B#7 Perforated to plug well 2 holes at 1840' 2 holes at 1050'	PERF	900.00T
	Sales Tax		99.90
		RECEIVED KANSAS CORPORATION COMMISSION MAR 13 2008 CONSERVATION DIVISION WICHITA, KS	

Thank you for your business. ████████████████████████████████████████████████████████████████████████████████	Total	\$1,899.90
------------------------------------------------------------------------------------------------------------------	--------------	------------