

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: DNR Oil & Gas, Inc.
Address: 12741 East Caley, Unit 142
Phone: (720) 482-1213 Operator License #: 30425
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: February 1, 2008 (Date)
by: Darrel Dipman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3858' Bottom: 3860' T.D. _____
Depth to Top: 3951' Bottom: 3953' T.D. _____
Depth to Top: 3998' Bottom: 4002' T.D. 4095'

API Number: 15 - 065-213³20 - 00 - 00
Lease Name: Blair
Well Number: 2 NE PKT CP2/3
Spot Location (QQQQ): 979 Feet from North / South Section Line
1747 Feet from East / West Section Line
Sec. 33 Twp. 8 S. R. 25 East West
County: Graham
Date Well Completed: December 1980
Plugging Commenced: January 30, 2008
Plugging Completed: February 19, 2008

Show depth and thickness of all-water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	252'	None
				4 1/2"	4088'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated casing at 2250' and 1425'. Pumped 200 sacks 60-40 Pozmix cement with 700 lbs. hulls at 2500'. Pumped 225 sacks 60-40 Pozmix cement with 250 lbs. hulls at 1200' Pumped 45 sacks 60-40 Pozmix cement down 8 5/8" casing. Put 30 sacks 60-40 Pozmix cement in 4 1/2" casing. Finished filling 4 1/2' casing with 1 1/2 yards Redi-mix cement

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 17 2008


Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 North Water Street, Suite 300, Wichita, KS 67202

CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: DNR Oil & Gas, Inc.
State of Colorado County, Arapahoe, ss.

J. M. Abell (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) J. M. Abell
(Address) 12741 East Caley, Unit 142, Centennial, CO 80111



SUBSCRIBED and SWORN TO before me this 12th day of March, 2008
Kerri Lea Kvachkov My Commission Expires: 11/17/11
Notary Public

[Handwritten signature]