

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: COMANCHE RESOURCES COMPANY
Address: 6520 N WESTERN AVE., SUITE 300
Phone: (405) 755-5900 Operator License #: 32384
Type of Well: D&A LH KCOPT 3/25/08 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/29/08 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
NONE Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-033-21509-00-00
Lease Name: MCKINNEY
Well Number: 5-1
Spot Location (QQQQ): S2-N2-NE-SW
2180' Feet from North / South Section Line
1980' Feet from East / West Section Line
Sec. 5 Twp. 31 S. R. 19 East West
County: COMANCHE
Date Well Completed: 1-30-08
Plugging Commenced: 1-30-08
Plugging Completed: 1-30-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				RECEIVED KANSAS CORPORATION COMMISSION MAR 17 2008 CONSERVATION DIVISION WICHITA, KS
Formation	Content	From	To	Size	Put In	
NONE		0	81'	20"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Lost circ. Mix mud. Work pipe. Run 1" pipe, wash down to 160'. LD 1" DC's, WO backoff tools & shot 3 times, collars backed off (shot @ 278').
LD DC's & Kelly. Run plug stands into well, circ & cond hole. Cmt plugs w/190 sks Class "A" (100 sks below bit & 90 to top of hole. See cementing record attached. Left 7 7/8" bit and 1 drill collar in hole. Bit is at approx. 308'


Name of Plugging Contractor: Fossil Drilling Inc. License #: 33610
Address: P.O. Box 464 Pratt, Kansas 67124-0464

Name of Party Responsible for Plugging Fees: Comanche Resources Company
State of Oklahoma County, Oklahoma, ss.

Dawn Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dawn Smith
(Address) 6520 N Western Avenue, Suite 300 Oklahoma City, OK 73116

SUBSCRIBED and SWORN TO before me this 12 day of March, 20 08
Laura Lea-Clayton My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRT

ALLIED CEMENTING CO., LLC. 31474

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT
Med Lodge
1-30-08

DATE <u>1-29-08</u>	SEC. <u>06</u>	TWP. <u>31s</u>	RANGE <u>19W</u>	CALLED OUT <u>6:30am</u>	ON LOCATION <u>10:00am</u>	JOB START <u>1:30pm</u>	JOB FINISH <u>2:30pm</u>
LEASE <u>McKinney</u>	WELL # <u>5-1</u>	LOCATION <u>Caldwater KB Sn</u>		COUNTY <u>Comanche</u>	STATE <u>Ks</u>		
OLD OR NEW (Circle one) <u>NEW</u>		<u>4 W 1/2 3/4 W 1/2 N ents</u>					

CONTRACTOR Fass: Drilling OWNER Comanche Res

TYPE OF JOB 1st Plug

HOLE SIZE 12 1/4 T.D. 286

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH 275

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 1 1/2 bbls water

EQUIPMENT _____

PUMP TRUCK # 372 CEMENTER Mark B

BULK TRUCK # 356 DRIVER Parlym

CEMENT			
AMOUNT ORDERED	<u>300 of 60/40 4 1/2 gel</u>		
	<u>1/2 Atlas seal</u>		
	<u>(used 220 of)</u>		
COMMON	<u>132 A</u>	@ <u>14.20</u>	<u>1874.40</u>
POZMIX	<u>88</u>	@ <u>7.20</u>	<u>633.60</u>
GEL	<u>8</u>	@ <u>18.75</u>	<u>150.00</u>
CHLORIDE		@	
ASC		@	
	<u>Flo Seal 55 #</u>	@ <u>2.25</u>	<u>123.75</u>
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>313</u>	@ <u>2.15</u>	<u>672.95</u>
MILEAGE	<u>50 X 313 X .09</u>		<u>1408.50</u>
			<u>TOTAL 4863.20</u>

REMARKS:

1st plug 100 of at 275 pump 5 bbls ahead, mix 14 1/2 bbls + Disp 15 bbls water

2nd plug 60 of at 82 ft pump 5 bbls ahead mix 9.5 bbls + disp 4.5 bbls

3rd plug circulate 2/D of to surface from 30ft + 15 of in rat hole

SERVICE

DEPTH OF JOB	<u>275'</u>		
PUMP TRUCK CHARGE			<u>917.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>50</u>	@ <u>7.00</u>	<u>350.00</u>
MANIFOLD		@	
	<u>Shawn Waiter</u>	@ <u>225.00</u>	<u>1800.00</u>
		@	

CHARGE TO: Comanche Res

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 3067.00

PLUG & FLOAT EQUIPMENT

ANY APPLICABLE TAX		
WILL BE CHARGED		
UPON INVOICING		
TOTAL		

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Scott Alberg

SIGNATURE [Signature]

SALES TAX (If Any)	
TOTAL CHARGES	<u>[Total]</u>
DISCOUNT	<u>[Discount]</u> IF PAID IN 30 DAYS

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 17 2008
CONSERVATION DIVISION
WICHITA, KS