

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Beren Corp.

Address: PO Box 723 Hays, KS 67601

Phone: (785) 628-6101 Operator License #: 5364

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3-3-08 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 4534 Bottom: 4558 T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-21017-00-00⁰¹

Lease Name: Levi

Well Number: 3725 OWWO 3

Spot Location (QQQQ): SESW. N.E.S.E. N.E.S.E. OPER

428 633 Feet from North / South Section Line

330 1153 Feet from East / West Section Line

Sec. 10 Twp. 16S S. R. 26 East West

County: Ness

Date Well Completed: 3-75

Plugging Commenced: 3-3-08

Plugging Completed: 3-3-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	oil, water	0	281	8-5/8	3-75	---
		0	4635	4-1/2	3-75	----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH W/ OPENENDED TBG TO 4100' MIX 35 SKS 60/40 4% GEL W/ 100# HULLS W/ GOOD RETURN. PULL 84 JTS TBG AT 1500' PMP 50# HULLS AND 40 SKS COMMON W/ 3% CC. TOH W/ TBG AND LET SET 1 HOUR, LOAD HOLE STAYING FULL, RIG UP PERFTECH AND SHOOT 2 HOLES AT 1200' GUN STUCK, WORK LOOSE, RIG UP TO 4-1/2" CSG AND MIX 135 SKS W/ 100# HULLS, CSG FULL, RIG UP TO 8-5/8 AND MIX 75 SKS 60/40 4% DOWN 8-5/8

RECEIVED

KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: H-D Oilfield Services License #: 32970

Address: PO Box 87 Bazine, KS 67516

MAR 17 2008


Name of Party Responsible for Plugging Fees: Mark Leiker w/ Beren Corp. CONSERVATION DIVISION WICHITA, KS

State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 10 day of March, 20 08
Shanna Miller My Commission Expires: 9-19-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials