

KANSAS CORPORATION COMMISSION

OIL & GAS CONSERVATION DIVISION **MAR 17 2008**

WELL PLUGGING RECORD

K.A.R. 82-3-117

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: FIML Natural Resources, LLC

Address: 410 17th Street Ste. 900

Phone: (303) 893-5090 Operator License #: 33476

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/27/2008 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Kansas City Depth to Top: 3947 Bottom: 3952 T.D. _____

Marmaton Depth to Top: 4384 Bottom: 4386 T.D. _____

Morrow Depth to Top: 4575 Bottom: 4579 T.D. _____

API Number: 15 - 171-20636-0000

Lease Name: Janssen

Well Number: 6-4-1931

Spot Location (QQQQ): _____ - C - SE - NW

1980 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 4 Twp. 19 S. R. 31 East West

County: Scott

Date Well Completed: 10/5/2006

Plugging Commenced: 2/28/2008

Plugging Completed: 2/28/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing/Kansas City	Oil & Water	0'	392'	8-5/8"	8/2/2006	
Marmaton	Oil & Water	0'	4766'	5-1/2"	8/7/2006	
Morrow	Oil & Water					
Mississippi	Oil & Water					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump 50 bbl fresh wtr down csg-no press. Mix & pump 200# hulls in 6 bbl water down casing. Mix & pump 40 sacks 60/40 poz w/ 100# hulls down casing. Mix & pump 10 sacks gel spacer in 25 bbl water down casing. Mix & pump 310 sacks 60/40 poz cement down casing-shut in with 150# standing. Hook up to backside (casing, surface pipe annulus) to 200#-no fluid pumped.

Job complete @ 12:20 p.m. Ken Jelik-State plugger on loc.

Name of Plugging Contractor: Allied Cementing Company License #: 115725 99996

Address: P.O. Box 31 Russell, KS

Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC

State of Colorado County, Denver, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) _____

(Address) 410 17th Street, Suite 900 Denver, CO. 80202

SUBSCRIBED and SWORN TO before me this 5th day of March, 20 08

Elaine Minich My Commission Expires: 5/5/2009
Notary Public

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



[Handwritten initials]

Additional Producing Formations:

Mississippian St Louis Top: 4588 Bottom: 4592
Mississippian Spergen Top: 4611 Bottom: 4613

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 17 2008

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

32153

RECEIVED
KANSAS CORPORATION COMMISSION

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

MAR 17 2008 SERVICE POINT:

Oakley

CONSERVATION DIVISION

DATE <u>2-28-08</u>	SEC <u>4</u>	TWP <u>19</u>	RANGE <u>31</u>	CALLED OUT	ON LOCATION <u>10:00 Am</u>	JOB START <u>11:30 Am</u>	JOB FINISH <u>12:30 pm</u>
LEASE <u>Janssen</u>	WELL # <u>6-4-1931</u>	LOCATION <u>scott city 9E 3/4 S E into</u>			COUNTY <u>scott</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR none OWNER same

TYPE OF JOB OHP

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. 3942-4613

DISPLACEMENT _____

CEMENT

AMOUNT ORDERED 375 sks 6 1/4 4 1/2 gel

300# Halls 10 gel on side

used 350 sks

COMMON	<u>280 sks</u>	@	<u>14.20</u>	<u>2982.00</u>
POZMIX	<u>140 sks</u>	@	<u>7.20</u>	<u>1008.00</u>
GEL	<u>24 sks</u>	@	<u>18.75</u>	<u>450.00</u>
CHLORIDE		@		
ASC		@		
	<u>Halls 6 sks</u>	@	<u>28.70</u>	<u>172.20</u>
		@		
		@		
		@		
		@		
HANDLING	<u>400 sks</u>	@	<u>2.15</u>	<u>860.00</u>
MILEAGE	<u>44 sk/mile</u>			<u>1980.00</u>
				TOTAL <u>7452.20</u>

EQUIPMENT

PUMP TRUCK CEMENTER Andrew

423-281 HELPER Alan

BULK TRUCK

373 DRIVER Larene

BULK TRUCK

_____ DRIVER _____

REMARKS:

Mix 40 sks with halls

10 sks gel for spacer followed

by 310 sks cement pressure

to 150 # shut back took

no cement pressured to

200#.

thank you

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 810.00

EXTRA FOOTAGE @ _____

MILEAGE 55 miles @ 7.00 385.00

MANIFOLD @ _____

@ _____

@ _____

TOTAL 1195.00

CHARGE TO: FIML

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

@ _____

@ _____

@ _____

@ _____

@ _____

TOTAL _____

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE E L Almon

PRINTED NAME