

15-065-00379-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 23 Twp. 10 Rge. 21 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW

Lease Owner Trans Era Petroleum, Inc.

Lease Name Sutor Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 4/19/53 19

Application for plugging filed 4/18/53 19

Application for plugging approved 4/18/53 19

Plugging commenced 4/19/53 19

Plugging completed 4/19/53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3905 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	170'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 165', set plug at 165', 15 sacks of cement mixed and run through drill pipe. Filled hole with mud to 40', set second plug together with 1/2 sack of hulls and 10 sacks of cement. Tied top plug

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert R. Michaelis

Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of April, 19 53

My commission expires 1-30-57

Magie Cooper Notary Public.

24-2675-S 2-52-20M

PLUGGING
FILE SEC 21 T 10 R 21W
BOOK PAGE 94 LINE 22

04-29-1953
DIVISION
Kansas



15-065-00379-00-00

Trans Era Petroleum, Inc.
Sutor #1

SW SW SW 21-10-21
Graham County, Ke.

Total Depth: 3905'
Comm. 4/7/53
Comp. 4/19/53

Casing

Cement

8 5/8" Set @ 170'

120 sacks Lone Star

Formation	Depth
Yellow clay	40
Shale-shells	176
Shale	618
Shale-shells	861
Sand	1030
Sand-shale	1405
Red bed-shale	1530
Red bed	1703
Anhydrite	1745
Shale-shells	1865
Shale	2110
Shale-shells	2589
Shale-lime	3445
Lime	3742
Lime-shale	3776
Lime	3834
Conglomerate	3851
Lime	3860
Arbuckle	3895
Lims	3905'

STATE OF KANSAS)
) 66
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Casa Belf

Subscribed and sworn to before me this 27th day of April, 1953.

Margie Cooper
Notary Public

My commission expires: 1-30-57.



PLUGGING
FILE SEC-21-10-R-21W
BOOK PAGE 94 LINE 22

RECORDED
STATE COMMISSION
APR 27 1953
04-29-1953
CONCEPTS DIVISION
VICTOR, TEXAS