

15-065-20194-00-00

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 27 Twp. 10S Rge. (E) 21 (W)

Location as "NE/CNWxSWx" or footage from lines SW NE NW

Lease Owner Robinowitz Oil Co.

Lease Name Lowell Well No. 3

Office Address 1322 E. 50th, Tulsa, Okla. 74105

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Dec. 28, 1968

Application for plugging filed Dec. 31, 1968

Application for plugging approved (by phone) Dec. 28, 1968

Plugging commenced Dec. 28, 1968

Plugging completed Dec. 28, 1968

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	246	8-5/8"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 875', set first plug @ 875' w/100 cu. ft. 50-50 pozmix plus 6% gel. Filled hole with heavy mud to 275', set second plug @ 275' w/20 cu. ft. cement. Filled hole with heavy mud to 40', set second plug @ 40' w/10 cu. ft. cement. Filled rat hole with 2 sacks cement. Job complete at 2:00 PM, Dec. 28, 1968. Job by Sun Cementing Co.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas

01-03-1969

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) E. E. Hall

830 Sutton Place - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 69

Barbara J. Layton  
Barbara J. Layton Notary Public.

Feb. 1, 1972



15-065-20194-00-00

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

LOWELL #3  
SW NE NW Section 27-10S-21W  
Graham County, Kansas

Commenced: December 16, 1968  
Completed: December 28, 1968

OPERATOR - Robinowitz Oil Co.

DEPTH		FORMATION	REMARKS
From	To		
0	247	Surface clay sand and shale	Ran 12 joints of 8-5/8" casing, set @ 246' w/150 sacks cement.
247	345	Shale	
345	800	Shale and sand	
800	1163	Shale and shells	
1163	1408	Dakota Sand	
1408	1685	Shale and red bed	
1685	1724	Anhydrite	
1724	1820	Shale	
1820	2757	Shale and lime	
2757	2825	Lime	
2825	3515	Lime and shale	
3515	3565	Lime	
3565	3630	Lime and shale	
3630	3812	Lime	
3812	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SW NE NW Section 27-10S-21W, Graham County, Kansas, to the best of my knowledge and belief.

*E. E. Hall*  
E. E. HALL


STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 2nd day of January, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

*Barbara J. Layton*  
Barbara J. Layton, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas

01-03-1969