


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-065-00231-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 27 Twp. 10 Rge. 21 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner John O. Farmer, Inc.  
Lease Name Noah "D" #1 Well No.  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 5-16-60 19  
Plugging completed 5-17-60 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Fabricius  
Producing formation Depth to top Bottom Total Depth of Well 3794 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	160'	none
				5-1/2"	3786'	747'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked in found hole bridged at 1200', drilled bridge out and filled w/sand to 3660' and dumped 3 sacks of cement with dump bailer. Pulled 5 1/2" casing, cleared hole and mudded the hole to 160', set rock bridge to 150' and dumped 25 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1960  
05-23-1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)


SUBSCRIBED AND SWORN to before me this 20th day of May, 19 60  
My commission expires 9-27-62  
Thomas V. Duggs Notary Public.



ADDRESS Russell, Kansas

Give detailed description and thickness of all formation drilled through, contents of sand, whether dry, water, oil or gas.

640 Acres  
N



Locate well correctly

COUNTY Graham, SEC. 27, TWP. 10S, RGE. 21W  
 COMPANY OPERATING JOHN O. FARMER, INC.  
 OFFICE ADDRESS Russell, Kansas  
 DRILLING STARTED 4/11, 1952, DRILLING FINISHED 5/25, 1952  
 DATE OF FIRST PRODUCTION \_\_\_\_\_ COMPLETED \_\_\_\_\_  
 WELL LOCATED NW 1/4 NW 1/4 SE 1/4, North of South  
 Line and \_\_\_\_\_ ft. East of West Line of Quarter Section  
 Elevation (Relative to sea level) DERRICK FLOOR 2198 GROUND, \_\_\_\_\_  
 CHARACTER OF WELL (Oil, gas or dryhole) Oil

OIL OR GAS SANDS OR ZONES

Name	From	To	Name	From	To
1			4		
2			5		
3			6		

Perforating Record If Any

Shot Record

Formation	From	To	No. of Shots	Formation	From	To	Size of Shot

CASING RECORD

Amount Set				Amount Pulled				Packer Record			
Size	Wt.	Thds.	Make	Ft.	In.	Ft.	In.	Size	Length	Depth Set	Make
8-5/8	24	8	LW	165				none			
5-1/2	17	8	LW	3820				None			

Liner Record: Amount \_\_\_\_\_ Kind \_\_\_\_\_ Top \_\_\_\_\_ Bottom \_\_\_\_\_

CEMENTING AND MUDDING

Size	Amount Set		Sacks Cement	Chemical		Method of Cementing	Amount	Mudding Method	Results (See Note)
	Ft.	In.		Gal.	Make				
8-5/8	165		100						
5-1/2	3820		100						

Note: What method was used to protect sands if outer strings were pulled? \_\_\_\_\_

NOTE: Were bottom hole plugs used? \_\_\_\_\_ If so, state kind, depth set and results obtained \_\_\_\_\_

TOOLS USED

Rotary Tools were used from \_\_\_\_\_ feet to \_\_\_\_\_ Cable tools were used from \_\_\_\_\_ feet to \_\_\_\_\_  
 \_\_\_\_\_ feet, and from \_\_\_\_\_ feet to \_\_\_\_\_ feet, and from \_\_\_\_\_ feet to \_\_\_\_\_

Type Rig \_\_\_\_\_

INITIAL PRODUCTION TEST

Describe initial test: whether by flow through tubing or casing or by pumping \_\_\_\_\_

Amount of Oil Production \_\_\_\_\_ bbls. Size of choke, if any \_\_\_\_\_ Length of test \_\_\_\_\_ Water

Production \_\_\_\_\_ bbls. Gravity of oil \_\_\_\_\_ Type of Pump if pump is used, describe \_\_\_\_\_

Formation	Top	Bottom	Formation	Top	Bottom
FARM NAME . . . . .			.NOAH "D" #1		
Shale & shells	0	1025			
Shale, shells & sand	1025	1625			
Shale & shells	1625	1675			
Anhydrite	1675	1715			
Shale & shells	1715	2360			
Lime & shale	2360	3510			
Lime	3510	3533			
Test	3533	3535			
Lime	3535	3571			
Lime & shale	3571	3595			
Lime	3595	3720			
Lime & shale	3720	3793			

I, the undersigned, being first duly sworn upon oath state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

*John O. Farmer*  
 Name and title of representative of company

Subscribed and sworn to before me this 19th day of May, 19 60

My Commission expires 10/11/62  
*Louise Quincy*  
 Notary Public.

WELL NO. 1 COUNTY Graham SEC. 27, TWP. 10S, RGE. 21W FARM NAME Noah "D"