

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,086-00-00

LEASE NAME Grecian "P"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 21 (X) or (W)

COUNTY Graham

Date Well Completed 6/6/79

Plugging Commenced 11-2-90

Plugging Completed 11-2-90

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/25/90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing/Ks City Depth to Top 3534 Bottom 3573 T.D. 3700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	207	-0-
				5 1/2	3838	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Old 5 1/2" csg. Squeeze at 1084' w 190 sks. New holes at 1150'-1240'. Tubing & rods stuck in hole. Shut tbq. & rods off at 3350'. Pulled tbq. & rods up to 2000'. Pumped 130 sks 65/35 Pozmix w/ 1070 gel down tubing. Circ to surface. Pulled tbq. & rods out of hole. Pumped 25 sks of same cement down 5 1/2 csg.
(If additional description is necessary, use BACK of this form.) - OVER-

Name of Plugging Contractor Allied Cementing Company License No. N/A

Address Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Graham, ss.

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 125 N. Market, Suite 1000
Wichita, KS 67202

RECEIVED SUBSCRIBED AND SWORN TO before me this 15th day of January, 19 91

STATE CORPORATION COMMISSION

01-06-1991

JAN 6 1991

My Commission Expires: 9/20/94

Danna Mckaig
Notary Public

Max psi 1000lbs. Shut in at 800 lbs. Pumped 60 sks same cement down
8 5/8 csg. max psi 500 lbs. Shut in at 500 lbs. Plugging witnessed
and approved by Carl Goodrow w/ KCC. Plugging complete at 8:30 p.m.