

15-065-20590-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Graham County, Sec. 32 Twp. 10S Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Tomlinson Oil Company
Lease Name MASTERS Well No. 1
Office Address 1030 Olive Garvey Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 3, 1973
Application for plugging filed (verbally) February 3, 1973
Application for plugging approved (verbally) February 3, 1973
Plugging commenced February 3, 1973
Plugging completed February 3, 1973
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3975 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set at 875' w/110 cu. ft.
2nd plug set at 245' w/30 cu. ft.
3rd plug set at 40' w/10 cu. ft.
Plug down at 9:00 a.m. 2-3-73.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1973
02-06-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 73

My commission expires February 10, 1975
Beverly Mann Notary Public.

CONTRACTOR'S WELL LOG

15-065 - 20590 - 00-00

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: MASTERS #1
 LOCATION: NW NW NW, Sec. 32-10S-21W
 Graham County, Kansas
 GEOLOGIST: Victor F. Reiserer
 SPUD DATE: January 25, 1973
 COMPLETION DATE: February 3, 1973

0	125	Clay and Rock
125	815	Shale
815	1010	Sand
1010	1240	Shale
1240	1485	Sand
1485	1740	Shale
1740	1783	Anhydrite
1783	2162	Shale
2162	2885	Lime & Shale
2885	3256	Lime
3256	3380	Lime & Shale
3380	3975	Lime
	3975	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 6 1973
 02-06-1973
 CONSERVATION DIVISION
 Wichita, Kansas

Drilled 227' of 12½" surface hole, set 8-5/8" surface casing at 225' K.B. w/175 sx. cement. Cement circulated. Plug was down at 8:15 p.m. 1-25-73.
 Dry and Abandoned

SAMPLE TOPS
 Anhydrite 1740
 B/Anhydrite 1783

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the MASTERS, #1, NW NW NW, Section 32-10S-21W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of February, 1973.

Beverly Mann
 Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975