STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-065-00343-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 33 Twp. 10 Rge. (E) 21 (W)

Location as "NE/CNW¼SW¼" or footage from lines SE SE SE

Lease Owner The Palmer Oil Corporation

Lease Name Noah Well No. 1

Office Address 415 Union Nat'l Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4/8/52 19

Application for plugging filed 4/8/52 19

Application for plugging approved 4/8/52 19

Plugging commenced 4/8/52 19

Plugging completed 4/8/52 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3935 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	153	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3935' to 140' - plug and 15 sax cement, heavy mud to 40' - plug and 10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Palmer Oil Corporation

Address 415 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

A. H. Smith (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Smith

415 Union Nat'l Bank Building, Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 52.

Iris Meyer
Notary Public.

My commission expires 7/23/55

23-8390-s 6-51—20M

PLUGGING
FILE SEC. 33 T. 10 R. 21 W
BOOK PAGE 8 LINE 3

04-16-1952

APR 16 1952

15-065-00343-00-00

WELL LOG - NOAH #1

WELL OWNER: The Palmer Oil Corporation

CONTRACTOR: The Palmer Oil Corporation

Commenced: 3/25/52
Completed: 4/8/52
RESULTS: Dry Hole

Location: SE SE SE
Sec. 33-10-21W
Graham County, Kansas
Elevation: 2209 R. B.

Casing Record

8 5/8" - 153' cemented 100 sacks

Shale	0	670	
Sand & shale	670	710	
Shale & shells	710	820	
Sand	820	910	
Shale & shells	910	1175	
Shale	1175	1190	
Sand	1190	1385	
Shale	1385	1684	
Anhydrite	1684	1734	
Shale	1734	1895	
Shale & lime	1895	3400	
Lime	3400	3430	
Lime & shale	3430	3500	
Lime	3500	3728	
Lime & shale	3728	3781	
Conglomerate	3781	3880	
Arbuckle lime	3880	3935	Rotary T. D.

Formation Tops (R. B.)

Heebner	3469
Lansing	3509
Base Kansas City	3730
Cherty Cong.	3846
Weathered Arb.	3861
Arbuckle	3880

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

By Edgar E. Smith

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in said County and State, this 15th day of April, 1952.

Iris Meyer
Notary Public

My Commission Expires: 7/23/55

PLUGGING
FILE SEC 33 T10 R21W
BOOK PAGE