

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Butler County, Sec. 18 Twp. 27S Rge. 3 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE 1/4 SW

Lease Owner J. P. Cady

Lease Name H.E. Boncher Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed Feb. 22, 1946 19

Application for plugging filed Feb. 22, 1946 19

Application for plugging approved Feb. 22, 1946 19

Plugging commenced Feb. 23, 1946 19

Plugging completed Feb. 23, 1946 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production --- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. L. Loman

Producing formation None Depth to top Bottom Total Depth of Well 3270 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				15 1/2	105	105
				13 5/8	1120	1120
				10"	2020	2020
				8"	2402	2402
				7"	2808	2808
				5 1/2"	3164	3164

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded back to 2150 feet, set 20 ft. rock bridge and cemented with 25 sacks; mudded back to 225 feet, set 15 foot rock bridge and cemented with 15 sacks; mudded back to 15 feet, set 10 foot rock bridge and cemented with 5 sacks, cement returning to base of collar.

FILE 18 27 3E
46 2
4/24/46
APR 24 1946
11:11 AM

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to J. P. Cady, c/o Lockheed Aircraft Corporation, Wichita, Kansas

Address

STATE OF Kansas COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ira Mackenke

(Address) Augusta Jones

SUBSCRIBED AND SWORN to before me this 23 day of March, 1946.

My commission expires March 17th 1948. Notary Public.

WELL LOG

J. P. Gaty, et al, Owner - Boucher #1

N. SW Section 18, Township 27, Range 3 E, Butler County, Kansas
 Figures indicate bottom of formation.

Spudded November 8, 1945
 Completed February 22, 1946

Pipe Record

15 1/2 105
 13 3/8 1120
 10" 2020
 8" 2315 UR 2402
 6 5/8" 2540 UR 2863
 5 1/2" 3164 pulled out
 Est. 2500 feet gas 2050-2070

Water Record

hfw 85-90
 2 bw 610-620
 1 bw 1335-1340
 2 bw 1465-1475
 1 1/2 bw 1885-1900
 4 bw 1910-1925
 hfw 2290-2295
 2 bw 2405-2415
 hfw 2470-2485
 hfw 2925-2935

0	to	70	Shale	1560	Shale
		100	Blue Shale	1585	Lime
		225	Shale	1595	Shale
		275	Lime	1625	Lime
		280	Shale	1645	Shale
		370	Lime	1655	Lime
		400	Shale	1660	Shale
		425	Lime	1695	Lime
		435	Shale	1705	Shale
		445	Lime	1750	Lime
		460	Shale	1770	Shale
		470	Lime	1785	Lime
		475	Red Rock	1820	Shale
		485	Shale	1845	Lime
		495	Lime	2007	Shale
		508	Shale	2020	Lansing Lime
		515	Lime	2025	Shale
		520	Shale	2095	Lime
		530	Lime	2210	Shale
		545	Shale	2225	Lime
		570	Lime	2250	Shale
		600	Shale	2290	Lime
		633	Lime	2295	Sandy Lime
		640	Light Shale	2320	Lime
		650	Blue Shale	2343	Shale
		655	Lime	2360	Lime
		680	Shale	2395	Shale
		705	Lime	2405	Shale and Shells
		745	Shale and shells	2500	Lime
		760	Lime	2505	Shale
		770	Shale	2535	Lime
		775	Lime	2540	Shale
		780	Blue Shale	2590	Lime
		785	Lime	2630	Shale
		790	Blue Shale	2645	Shale and Shells
		810	Lime	2670	Shale
		953	Shale	2700	Lime
		960	Lime	2750	Shale and Shells
		990	Blue Shale	2775	Lime
		1000	Grey Shale	2780	Shale
		1125	Shale	2795	Lime Shells
		1160	Lime	2815	Shale
		1180	Shale and Shells	2825	Lime - some chert
		1185	Lime	2850	Vari-colored Shale
		1195	Light Shale	2858	Vari-colored Shale and Shells
		1215	Blue Shale	2871	Lime
		1220	Light Shale	2875	Dolomite Cherty
		1230	Lime	2882	Green Lime and Shale
		1315	Shale	2890	Shale and Shells
		1365	Lime	2905	Lime and Chert
		1375	Shale	3098	Lime
		1390	Lime	3102	Light Shale
		1450	Shale	3120	Dark Shale
		1493	Lime	3140	Black Shale
		1520	Shale	3150	Dark Shale
		1540	Lime	3153	Crown Lime, soft, viola

21110-21115
 FILE 18 27 3E
 BOOK 46 2

APR 24 1946

Boucher #1


3171	Simpson Sand
3195	Lime and Shale
3210	Lime
3215	Shale
3225	Sand
3235	Sandy Lime
3245	Shale
3255	Sand
3270	Lime
3270	Total Depth

STATE OF KANSAS)
) SS
 COUNTY OF BUTLER)


I, Ira Markenke, Drilling Contractor of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed and that the same are true and correct.

Ira Markenke

Subscribed and Sworn to before me this 23 day of March, 1946.



J. J. Dickham
 Notary Public



FIL 18 27 3E
 46 2