

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: PETROLEUM PROPERTY SERVICES INC.

Address: 125 N. MARKET, SUITE 1251, WICHITA KS 67202

Phone: (316) 265-3351 Operator License #: 31142

Type of Well: OIL Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/13/08 (Date)

by: RICHARD LACEY (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No

Producing Formation(s): List All (If needed attach another sheet) MISS Depth to Top: 4470 Bottom: 4495 T.D. 4496

API Number: 15-135-21505-00-00

Lease Name: STUTZ

Well Number: 2

Spot Location (QQQQ): C - NE - NW -

660 Feet from [X] North / [] South Section Line

1980 Feet from [] East / [X] West Section Line

Sec. 5 Twp. 17 S. R. 25 [] East [X] West

County: NESS

Date Well Completed: 10/01/78

Plugging Commenced: 2/14/08

Plugging Completed: 2/14/08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: MISS, OIL&WATER, 4470, 4495, 8-5/8", 252, 0. Row 2: (blank), (blank), (blank), (blank), 5-1/2, 4470, 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

PUMP 30 SX 60/40 W/100# HULLS DOWN TBG. PULL UP TO 1500' & PUMP 50 SX 60/40 W/50# HULLS. PULL UP TO 1200' MIX 28 BBL AND PUMP DOWN BACKSIDE. MIX 7 BBL CEMENT TO SURFACE AND TOP OFF WITH 2-1/2 BBL CEMENT. USED 287 SX AND 150# HULLS AND 2 SX CC

RECEIVED KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: H-D OILFIELD SERVICE, INC. License #: 32970

MAR 07 2008

Address: P O BOX 87, BAZINE KS 67516

CONSERVATION DIVISION WICHITA, KS

Name of Party Responsible for Plugging Fees: PETROLEUM PROPERTY SERVICES INC.

State of KANSAS County, SEDGWICK, ss.

MICHEAL S. MITCHELL (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 125 N. MARKET, SUITE 1252, WICHITA KS 67202

ROSANN M. SCHIPPER, NOTARY PUBLIC, STATE OF KANSAS, My Appt. Exp. 9/28/11

SUBSCRIBED and SWORN TO before me this 5TH day of MARCH, 20 08. Rosann M Schippers, Notary Public, My Commission Expires: 9/28/11

[Handwritten initials]