

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Vincent Oil Corporation
Address: 155 N. Market, Suite 700
Phone: (316) 262-3573 Operator License #: 5004
Type of Well: D&A Docket #:
The plugging proposal was approved on: 01-14-08
by: Jerry Stapleton (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 097-21624-0000
Lease Name: Fisher
Well Number: 1-9
Spot Location (QQQQ): 75' W - E/2 - W/2
2640 Feet from North / South Section Line
3375 Feet from East / West Section Line
Sec. 9 Twp. 27 S. R. 17 East West
County: Kiowa
Date Well Completed:
Plugging Commenced: 01-15-08
Plugging Completed: 1-15-08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 0', 440', 8 5/8", 440', 0'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole filled with drilling mud, spotted cement plugs through drill pipe

1st plug: 50 sx @ 1140'

2nd plug: 50 sx @ 450'

Top plug: 20 sx @ 60'; 15 sx in Rathole & 10 sx in Mousehole

RECEIVED KANSAS CORPORATION COMMISSION

MAR 07 2008

Name of Plugging Contractor: Duke Drilling Co. Inc License #: 5929

Address: P.O. Box 823, Great Bend, Kansas 67530

CONSERVATION DIVISION WICHITA, KS

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation

State of Kansas County, Sedgwick, ss.


Rick Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Richard H. Hiebsch

(Address) 155 N. Market, Suite 700, Wichita, Kansas

SUBSCRIBED and SWORN TO before me this 6th day of March, 2008

Yolanda Eubanks Notary Public My Commission Expires:



# ALLIED CEMENTING CO., LLC. 31395

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Medicine Lake, KS

DATE <u>15 Jan 08</u>	SEC. <u>09</u>	TWP. <u>27s</u>	RANGE <u>17w</u>	CALLED OUT <u>9:00 Am</u>	ON LOCATION <u>2:30pm</u>	JOB START <u>5:30pm</u>	JOB FINISH <u>7:00 pm</u>
LEASE <u>Fisher</u>	WELL # <u>1-9</u>	LOCATION <u>Hawilard, KS 6 1/4 N, 5 1/2 W, 1 1/2 N</u>			COUNTY <u>Kiowa</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)			<u>&amp; E, take Right Fork</u>				

CONTRACTOR Duke #1  
 TYPE OF JOB Rotary Plug  
 HOLE SIZE 7 7/8 T.D. 4725  
 CASING SIZE 8 5/8 DEPTH 440  
 TUBING SIZE DEPTH  
 DRILL PIPE 4 1/2 DEPTH 1140  
 TOOL DEPTH  
 PRES. MAX 300 MINIMUM  
 MEAS. LINE SHOE JOINT N/A  
 CEMENT LEFT IN CSG.  
 PERFS.  
 DISPLACEMENT Fresh H<sub>2</sub>O & mud

OWNER Vincent oil  
 CEMENT  
 AMOUNT ORDERED 155 sx 60:40:4

EQUIPMENT  
 PUMP TRUCK CEMENTER D. Felio  
 # 352 HELPER M. Becken  
 BULK TRUCK  
 # 363 DRIVER R. Franklin  
 BULK TRUCK  
 # DRIVER

COMMON	<u>93</u>	<u>A</u>	@	<u>14.20</u>	<u>1320.60</u>
POZMIX	<u>62</u>		@	<u>7.20</u>	<u>446.40</u>
GEL	<u>5</u>		@	<u>18.75</u>	<u>93.75</u>
CHLORIDE			@		
ASC			@		
HANDLING	<u>160</u>		@	<u>2.15</u>	<u>344.00</u>
MILEAGE	<u>30</u>	<u>X 160</u>	<u>X .09</u>		<u>432.00</u>
					TOTAL <u>2636.75</u>

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 07 2008  
CONSERVATION DIVISION  
WICHITA, KS

REMARKS:

Pipe at 1140, Fill Hole Pump 8 1/2 Bbls Fresh H<sub>2</sub>O, Spacer, Mix 50sx 60:40:4 cement, Disp. 3 Bbls Fresh H<sub>2</sub>O & 9 1/2 Bbls Mud, Pipe at 450, Pump 8 Bbls Fresh H<sub>2</sub>O spacer, Mix 50sx 60:40:4 cement, Disp. 3 Bbls Fresh H<sub>2</sub>O, Pipe at 60, Fill Hole, Mix 20sx 60:40:4 cement, Plug Rat Hole w/ 15sx Cement, Plug Mouse Hole w/ 10sx Cement, Plug Water Well w/ 10sx Cement,

CHARGE TO: Vincent oil co.  
 STREET  
 CITY STATE ZIP

SERVICE

DEPTH OF JOB	<u>1140</u>		
PUMP TRUCK CHARGE			<u>912.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>30</u>	@	<u>7.00</u> <u>210.00</u>
MANIFOLD		@	
		@	
		@	
			TOTAL <u>1127.00</u>

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SALES TAX (If Any)	
TOTAL CHARGES	<del>2636.75</del>
DISCOUNT	<del>2636.75</del> IF PAID IN 30 DAYS

PRINTED NAME Mike Godfrey  
 SIGNATURE Mike Godfrey