

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Vincent Oil Corporation

Address: 155 N. Market, Suite 700

Phone: (316) 262-3573 Operator License #: 5004

Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 01-02-08 (Date)

by: Eric McLaren (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 097, 21619-0000

Lease Name: Mull

Well Number: 5-1

Spot Location (QQQQ): _____ - _____ - NW - SW
1980 Feet from North / South Section Line

660 Feet from East / West Section Line

Sec. 1 Twp. 27 S. R. 17 East West

County: Kiowa

Date Well Completed: _____

Plugging Commenced: 01-04-08

Plugging Completed: 01-04-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	416'	8 5/8"	416'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole full of mud, spotted cement plugs through drill pipe

1st plug: 50 sx @ 1140';

2nd plug: 50 sx @ 450'

Top plug: 20 sx @ 60'; with 15 sx in Rathole & 10 sx in Mousehole; Plugs down @ 3:00PM 1/04/08

Name of Plugging Contractor: Duke Drilling Co. Inc. License #: 5929


Address: P.O. Box 823 Great Bend, Kansas 67530

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation

State of Kansas County, Sedgwick, ss.

Rick Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 155 N. Market, Suite 700, Wichita, Kansas

SUBSCRIBED and SWORN TO before me this 6th day of March, 2008

Yolanda Eubanks My Commission Expires: 10-9-09
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 07 2008
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]

ALLIED CEMENTING CO., LLC. 31388

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge, KS

DATE <i>04/5/07</i>	SEC. <i>01</i>	TWP. <i>27s</i>	RANGE <i>17w</i>	CALLED OUT <i>8:00 AM</i>	ON LOCATION <i>11:30 AM</i>	JOB START <i>12:00 PM</i>	JOB FINISH <i>3:00 PM</i>
LEASE <i>Mull</i>		WELL # <i>5-1</i>		LOCATION <i>Haviland, KS, 7N, 1W, 1/4 SW, 1/4 NW</i>		COUNTY <i>Kiowa</i>	STATE <i>KS</i>
OLD OR <u>NEW</u> (Circle one)				<i>w/n/into</i>			

CONTRACTOR *Duke #1*

TYPE OF JOB *Rotary Plug*

HOLE SIZE *7 7/8* T.D. *4720*

CASING SIZE *8 5/8* DEPTH *417*

TUBING SIZE DEPTH

DRILL PIPE *4 1/2* DEPTH *1140*

TOOL DEPTH

PRES. MAX *250* MINIMUM *-*

MEAS. LINE SHOE JOINT *N/A*

CEMENT LEFT IN CSG. *-*

PERFS.

DISPLACEMENT *Fresh H₂O + Mud*

OWNER *Vincent oil*

CEMENT:

AMOUNT ORDERED *145 sx 60:40: + 4% gel*

COMMON	<i>Class A 87sx @ 11.10</i>	<i>965.70</i>
POZMIX	<i>58 sx @ 6.20</i>	<i>359.60</i>
GEL	<i>5 sx @ 16.65</i>	<i>83.25</i>
CHLORIDE	@	
ASC	@	

EQUIPMENT

PUMP TRUCK CEMENTER *D. Felix*

352 HELPER *M. Becker*

BULK TRUCK

363 DRIVER *L. Freeman Jr.*

BULK TRUCK

DRIVER

HANDLING	<i>150 @ 1.90</i>	<i>285.00</i>
MILEAGE	<i>150/30/.09</i>	<i>405.00</i>
TOTAL		<i>2098.55</i>

RECEIVED
KANSAS CORPORATION COMMISSION
@
MAR 0 @ 2007
@
CONSERVATION DIVISION
WICHITA, KS
@
@
@

REMARKS:

Pipe at 1140, Pump 8 1/2 Bbls Fresh H₂O spacer, mix 50sx Cement, Disp. w/ 3 Bbls Fresh & 9 Bbls Mud, Pipe at 450, Pump 9 Bbls Fresh H₂O spacer, mix 50sx Cement, Disp. w/ 3 Bbls Fresh H₂O, Plug at 60' w/ 20sx Cement, Plug Rest Hole w/ 15sx Cement, Plug Mouse Hole w/ 10sx Cement

CHARGE TO: *Vincent oil Co.*

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<i>1140</i>	
PUMP TRUCK CHARGE		<i>815.00</i>
EXTRA FOOTAGE	@	
MILEAGE	<i>30 @ 6.00</i>	<i>180.00</i>
MANIFOLD	@	
	@	
	@	
TOTAL		<i>995.00</i>

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
APPLICABLE TAX WILL BE CHARGED UPON INVOICING		
TOTAL		<i>995.00</i>
SALES TAX (If Any)		
TOTAL CHARGES		<i>995.00</i>
DISCOUNT		IF PAID IN 30 DAYS

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *Mike Godfrey*

SIGNATURE *Mike Godfrey*