

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Charter Energy, Inc.
Address: P.O. Box 252 Great Bend, Ks 67530
Phone: (620) 793-9090 Operator License #: 9090
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 2/13/08 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3610 Bottom: 3850 T.D. _____
Marmaton Depth to Top: 3931 Bottom: 3970 T.D. 4014

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-21591-00-00
Lease Name: Kline Shaw Creek Unit #2
Well Number: #2 *KCC per CP2/3*
Spot Location (QQQQ): SE - SE - NW -
2970 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 28 Twp. 11 S. R. 22 East West
County: Trego
Date Well Completed: 1984
Plugging Commenced: 2/18/08
Plugging Completed: 2/18/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	300	8 5/8	300	0
		0	4014	4 1/2	4014	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing to 3804. Pump 13sx gel w/ hulls followed by 40 sx 60/40 4% w/ hulls. Pull tubing to 1600. Pump 130sx w/525 hulls and circulated hole.

Pulled tubing. Top well off w/ 15sx. Tie onto 8 5/8. Pump 5 sx and pressured up. Plugging complete.

KCC per CP2/3

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: SWIT Professional Pulling Services LLC License #: 32382 32810 **MAR 06 2008**

Address: Ness City, KS CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Charter
State of Kansas County, Barton, ss.

Steve Baize (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) *[Handwritten Signature]*

(Address) P.O. Box 252 Great Bend, Ks 67530

SUBSCRIBED and SWORN TO before me this 5th day of March, 20 08

Donna Moore My Commission Expires: 2-17-2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



[Handwritten initials]

JOB LOG

SWIFT Services, Inc.

DATE 02-18-08 PAGE NO. 1

CUSTOMER CHARTER ENERGY WELL NO. 2 LEASE WINE JOB TYPE PTA TICKET NO. 13259

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1500							ON LOCATION, STOP, DISCUSS JOB CMT 200 60-10 4% GEL, GEL INSIDE 1354 2 3/8 X 4 1/2 TO 4015, 8 5/8 @ 300
	1515	3.0	0	✓		0		START GEL TBG @ 3804 <u>1354 GEL</u>
		3.0	20	✓		300		START TO CIRC
		3.0	30	✓		400		" HULLS <u>225*</u>
		3.0	40	✓		500		END GEL, START CMT w/ HULLS <u>40 5/8 CMT</u>
	1535	3.0	510	✓		500		END CMT Pull TBG up to 1600 FT
	1615	3.0	0	✓		0		START CMT w/ HULLS
	1627	3.0	350	✓		300		CIRC CMT <u>130 SKS CMT</u> Pull TBG OUT <u>w/ 505* HULLS</u>
	1700		1.0	✓		300		TIE ON 8 5/8 <u>5 SKS CMT</u>
	1715		0	✓				HOOR ON 4 1/2
			5.0	✓				4 1/2 FULL <u>15 SKS CMT</u>
								WASH UP <u>TOTAL CMT 185</u>
								Recup " GEL 13
								TICKETS " HULLS 750
	1800							JOB COMPLETE
								THANK YOU! Dave, JERRB, Ryan

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 06 2008

CONSERVATION DIVISION
WICHITA, KS