

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Charter Energy, Inc.

Address: P.O. Box 252 Great Bend, Ks 67530

Phone: (620) 793-9090 Operator License #: 9090

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/20/08 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Depth to Top: 3581 Bottom: 3820 T.D. _____
Marmaton Depth to Top: 3905 Bottom: 3944 T.D. 4016
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-21184-00-00

Lease Name: Berens-Rice Shaw Creek Unit

Well Number: BR-10

Spot Location (QQQQ): SW - NE - SW -

1650 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 28 Twp. 11 S. R. 22 East West

County: Trego

Date Well Completed: 1983

Plugging Commenced: 2/20/08

Plugging Completed: 2/20/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	263	8 5/8	263	0
		0	3990	4 1/2	3990	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 3930. Pump 100sx 60/40 4% w/300 hulls. Pull tubing to 2175. Pump 125sx w/300 hulls, circulated cement to surface.

Pulled tubing. Top well off w/ 25sx. Tie onto 8 5/8. Pressured to 200# and held. Plugging complete.

KCC PRF PERC P 2/3

Name of Plugging Contractor: Swift Professional Pulling Services LLC License #: 32382 RECEIVED KANSAS CORPORATION COMMISSION

Address: Ness City, KS

MAR 06 2008

Name of Party Responsible for Plugging Fees: Charter

State of Kansas County, Barton, ss.

CONSERVATION DIVISION
WICHITA, KS


Steve Baize (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 252 Great Bend, Ks 67530

SUBSCRIBED and SWORN TO before me this 5th day of March 20 08

Donna Moore Notary Public My Commission Expires: 2-17-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PRF

JOB LOG

SWIFT Services, Inc.

DATE 02-20-08 PAGE NO. 1

CUSTOMER CHARTER ENERGY WELL NO. 10 LEASE BARENS RISE JOB TYPE PTA TICKET NO. 13260

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1530							OPERATIONAL SETUP, DISCUS TOP, RUNNING TBL CMT 32560-40 4% CCL, 800# HULLS 2 3/8 x 4 1/2 4 1/2 TO 3990 8 5/8 e 263
	1620	4.5	0	✓		0		START CMT w/ HULLS, TBL @ 3930
		4.5	70	✓		600		CIRC
		4.5	260	✓		600		END CMT CMT 100 SWS
		4.5	0	✓		600		ST DISP 300# HULLS
		4.5	6	✓		600		END
								PULL TBL TO 2175
	1705	4.5	0	✓		500		START CMT w/ HULLS
		4.5	5	✓		700		CIRC
		4.5	30	✓		700		CIRC CMT FLAG CMT 12.5 SWS
		4.5	32	✓		700		" 170 300# HULLS
	1715	4.5	37	✓		700		CIRC @ 600 CMT, END
								PULL TBL OUT
	1815							
	1815		0.1	✓		000		Pump Down 8 5/8 HULL
	1840		6.0	✓				TOP 4 1/2 CMT 25 SWS
								TOTAL CMT
								250 SWS
								600# HULLS
								WASITUP
								TICKETS
	1915							JOB COMPLETE
								THANK YOU!
								DAVE JOSH, ROB

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 06 2008

CONSERVATION DIVISION
WICHITA, KS