

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22925-00-00
Spot: NWNENW Sec/Twnshp/Rge: 19-14S-19W
4990 feet from S Section Line, 3487 feet from E Section Line
Lease Name: BARNES Well #: 1
County: ELLIS Total Vertical Depth: 3813 feet

Operator License No.: 30961
Op Name: A P S, INC.
Address: 750 MT PLEASANT RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3812	0	w/150 sxs cmt
SURF	8.625	265	0	w/165 sxs cmt

123.92

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/03/2008 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: WILLIE BARNES Company: APS, INC. Phone: (785) 625-5361

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 600# hulls.
CIBP at 3489'. Casing leak at 2870'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2008 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2838' - pumped 100 sxs cement with 400# hulls.
Pulled tubing to 1381' - pumped 75 sxs cement with 200# hulls - good circulation of cement.
Pulled tubing out - tied onto backside - pumped 15 sxs cement.
Max. P.S.I. 200#. Shut in.
Filled casing down the top with 75 sxs cement. Standing full.

Perfs:

INVOICED
DATE 3-20-08
INV. NO. 2008061377

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 07 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #30179.

Plugged through: TBG

District: 04

Signed 

(TECHNICIAN)

MAR 04 2008

TRIPLE H. OIL OPERATIONS
 P. O. BOX 248
 HAYS, KS 67601

REPLACEMENT CARD
 #1 BARNES

19-14-19W
 300' FNL &
 760' FEL, NW/4

CONTR DREILING OIL COMPANY CITY ELLIS

GEOL _____ FIELD PLEASANT SE EXT
 (1/8 S)

ELV 2194 KBSPD 3/12/82 CARD ISSUED 4/14/83 IP P 13 BO & 20 BWPD
2189 GL
 API 15-051-22,925 LKC 3624-3680 OA
MARM 3790-3300
 (NEW PAY - LKC OIL)

+	+
+	+
+	+

DRLRS	Top	Depth/Datum
ANH		1459 + 735
B/AHN		1503 + 691
NO OTHER TOPS AVAILABLE		
RTD		3813-1619

8 5/8 " 265 / 165SX; 4 1/2 " 3812 / 150SX
 NO DST'S
 MICT - CO, PF (MARM) 3790-3800, W/2 SPF. & PF (LKC) 3674-
 80, 3624-28, W/2 SPF, A3-1500G (15%), SWB LD, SO, T & R,
 POP, COMMINGLED, P 13 BO & 20 BWPD, 7/27/83 - NO OTHER
 INFO RELEASED BY OPERATOR

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

INFO RELEASED: 5/31/84 - WAS OIL WELL - TIGHT HOLE