

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23689-00-00  
Spot: NENW Sec/Twnshp/Rge: 32-6S-20W  
610 feet from N Section Line, 1770 feet from W Section Line  
Lease Name: MCCLURG Well #: 4  
County: ROOKS Total Vertical Depth: 3478 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		

113.04

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/21/2008 11:30 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.  
Bottom joint of surface pipe separated from stringed.  
Reamed at 188' and finally fell into old wellbore - decided to P&A.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE  
Date/Time Plugging Completed: 02/21/2008 1:00 PM KCC Agent: HERB DEINES


Actual Plugging Report:  
1st. Plug at 1875' w/25 sxs.  
2nd. Plug at 1150' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Perfs:  
**INVOICED**  
DATE 3-20-08  
INV. NO. 2008061378

RECEIVED  
KANSAS CORPORATION COMMISSION  
**MAR 07 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: DP

District: 04

Signed   
(TECHNICIAN)

MAR 03 2008

