

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-19102-00-01  
Spot: SEWNWE Sec/Twnshp/Rge: 36-4S-20W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SLINKER Well #: 403W  
County: PHILLIPS Total Vertical Depth: 3331 feet

Operator License No.: 31763  
Op Name: BLAKE PRODUCTION CO., INC.  
Address: 1601 NW EXPRESSWAY STE 1200  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3330	0	200 SX
SURF	8.625	276	0	250 SX

108-26

Well Type: EOR UIC Docket No: E13967.3 Date/Time to Plug: 02/21/2008 10:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: TERRY GARRISON Company: BLAKE PRODUCTION CO., INC. Phone: (785) 216-0588

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 1000# hulls.  
DV Tool at 1475' w/400 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/21/2008 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3174' - pumped 210 sxs 60/40 pozmix - 4% gel with 500# hulls - had circulation with 400# P.S.I.  
Pulled tubing to 1000' - pumped 40 sxs 60/40 pozmix - 4% gel - had circulation.  
Pulled all tubing - pumped 10 sxs 60/40 pozmix - 4% gel to fill 4 1/2" casing.  
Hooked onto backside and pumped 5 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3079	3263		

**INVOICED** 9  
DATE 3-20-08  
INV. NO. 2008061380

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 07 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: LEASE ALSO KNOWN AS LYNCH #3. QUALITY OIL WELL CEMENTING, INC.

Plugged through: TBG

District: 04

110

Signed

Pat Bedore

(TECHNICIAN)

FEB 27 2008

*[Handwritten signature]*

CITIES SERVICE OIL CO.

#3 LYNCH

36-4-20W  
SE NW NE

Contr. LEBEN DR LG

City: PHILLIPS

Geol.

Pool SLINKER

E. 1939 KB Cm. 11/18/64 Cp. 12/17/64 IPP 48 BOPD + 16 BW  
KC 3079-3184

LOG Tops	Depth	Datum
*ANHY	1460	+ 479
*B/ANHY	1490	+ 449
HEEB	3048	-1109
TOR	3076	-1137
LKC	3094	-1155
BKC	3304	-1365
RID	3331	-1392
*SMP TOP		

Csg. 8" 275/250 SX, 4" 3330/200  
DV TOOL 1430

NO DSTS

CO 3312, PF 1/3183, 1/3172, 1/  
3169, 1/3131, 1/3079, A 2000, 6/  
3182-84, 15/3168-73, 9/3129-32,  
6/3079-80, SET TBG, PMP 60 BW/20  
HRS, PMP 54 80 + 18 BW/24 HRS,  
PMP 46 80 + 7 BW/24 HRS, (SHORT  
83 BBLs LD WTR)

CORRECTED CARD: 8/15/68

WAS SE NW SE  
IS SE NW NEINDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS