

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21702-00-00
Spot: SENWNENW Sec/Twnshp/Rge: 26-13S-30W
460 feet from N Section Line, 1960 feet from W Section Line
Lease Name: WESLEY Well #: 3
County: GOVE Total Vertical Depth: 4620 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	328		

150.15

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/02/2008 4:30 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: TIM FABRICIUS Company: VAL ENERGY, INC. Phone: (316) 262-1378

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 03/02/2008 7:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2315' w/25 sxs.
2nd. Plug at 1325' w/100 sxs.
3rd. Plug at 375' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 3-20-08
INV. NO. 2008061383

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 07 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

MAR 04 2008

PST