

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01358-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 8-9S-21W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SWENSON B Well #: 3
County: GRAHAM Total Vertical Depth: 3811 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3808	0	125 SX
SURF	8.625	153	0	125 SX

123.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2008 8:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 1000# hulls - 15 sxs gel.
Perf Tech perf at 1825' and 1050'. OH 3808'. High fluid level.
Holes 2635'-2667' squeeze w/250 sxs.
Tite holes at 1043'-1075' - not squeezed - some junk in bottom of hole - tubing, rods, and pump sanded in.
Dakota 717'-1017'. Anhy 1810'-1833'. Salt 2149'-2236'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2008 1:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Poe RIH with tubing to 3600'. Allied rigged to tubing - pumped 15 sxs gel, followed with 40 sxs 60/40 pozmix with 250# hulls mixed in.
Pulled tubing to 1850'. Allied rigged to tubing - pumped 130 sxs 60/40 pozmix - 4% gel with 750# hulls mixed in - circulated cement into pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 20 sxs 60/40 pozmix - 4% gel. Max. P.S.I. 400#. S.I.P. 400#.
Rigged to 8 5/8" - pumped 5 sxs cement - blew small hole in top of head. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3542	3548		

INVOICED

DATE 3-20-08
INV. NO. 2008061384

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 07 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #3180.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)


Handwritten initials

BARNETT OIL & DERBY OIL #3 SWENSON 'B' 8-9-21W
 NW NW SW
 GRAHAM County

Contr. E 2297 RB Comm. ^K 12-20-53 TD 12-29-53 Comp. 2-19-54 IP 3000 BOPD
 DRAW DOWN

Tops	Depth	Datum
LANS	3503	-1206
ARB	3807	-1510
TD	3811	-1514

Casing
 8" 153
 5" 3808
 CO 3811: SWB 23
 BO/3 HR



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS