

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21678-00-00  
Spot: NENWSESW Sec/Twnshp/Rge: 23-20S-12W  
990 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: KRUEGER B Well #: 2  
County: BARTON Total Vertical Depth: 3358 feet

Operator License No.: 31647  
Op Name: CHURCHILL, KIM DBA K.C. OPERATIONS  
Address: 534 SE 70 AVE  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3352	2460	w/150 sxs cmt
SURF	8.625	219	0	w/225 sxs cmt

109.14

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2008 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2008 11:30 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:  
Sanded to 3100' - topped with 5 sxs cement - cut casing at 2460'.  
Pulled casing to 1425' - tied onto casing - pumped 140 sxs cement with 300# hulls.  
Pulled to 600' - pumped 60 sxs cement with 100# hulls.  
Pulled to 40' - pumped 100 sxs cement with 100# hulls.  
Pulled casing - stayed full.

Perfs:

**INVOICED**  
DATE 3-2008  
INV. NO. 2008061387

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 07 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING.  
Plugged through: CSG

District: 04 Signed Bruce Rodie  
(TECHNICIAN)

FEB 28 2008

WICHITA  
 2-11-79  
 10-6-79  
 10-6-79

ALPINE DRILLING CO. INC.  
 300 BITTING BLDG  
 WICHITA, KS 67202

B- #2 KRUEGER

23-20-12W  
 100' SW,  
 C E/2 SW

CONTR HUSKY DRLG. CO. CTY BARTON

GEOLOGIST JEFF BURK FIELD CRUE

E 1810 KB CM 8/20/79 CARD ISSUED 10/20/79 IP P 22 BOPD, NW

ARB OH 3352-65

API 15-009-21,678

+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
HEEB	2979	-1169	
TOR	2996	-1186	
DG	3011	-1201	
BR LM	3105	-1295	
LANS	3122	-1312	
B KC	3303	-1493	
ARB	3341	-1531	
LTD	3352	-1542	
RTD	3358	-1548	
DDTD	3365	-1555	

8-5/8" 219/225sx, 4 1/2" 3352  
 DST (1) 3151-3180 (KC)/30-45-30-45, REC  
 5' M, SIP 46-46#, FP 23-23/23-23#  
 DST (2) 3244-3264 (KC)/30-30-30-30, REC  
 5' M, SIP 46-46#, FP 23-23/23-23#  
 DST (3) 3324-3354 (ARB)/30-45-30-30,  
 REC 15' M, SIP 46-46#, FP 23-23/23-  
 23#  
 DST (4) 3347-3358 (ARB)/30-45-60-45,  
 REC 480' G, 255' M&GCO, SIP 832-  
 762#, FP 46-69/92-138#  
 MICT - CO, (ARB OH), DD 3360 TD, SL  
 INCR IN O, FU 400' O, AC 500 (15%),  
 SWB 1 BFPH, MOSTLY OIL, NO INCR, DD  
 3362 TD, CHTY, NO INCR, DD 3365 TD, FU  
 200' O/2HRS, ONFU 300' O, NW, SWB 2.5  
 BOPH/6HRS, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS