

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01688-00-01
Spot: SWSE Sec/Twnshp/Rge: 1-14S-15W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: A DUMLER B Well #: 1
County: RUSSELL Total Vertical Depth: 3295 feet

Operator License No.: 31431
Op Name: BARTON EXPLORATION, INC.
Address: 3017 E 14TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3295	0	75 SX
SURF	10.75	349	0	200 SX

107.09

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2007 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: LONNIE BARTON Company: BARTON EXPLORATION, INC. Phone: (785) 483-9136

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2007 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Backside had been squeezed.
Ran tubing to 2864' - pumped 17 sxs gel followed with 50 sxs 60/40 pozmix - 4% gel cement with 200# hulls.
Pulled to 1000' - circulated with 95 sxs cement with 300# hulls.
POOH. Tied onto casing and pumped 5 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.

INVOICED
DATE 11-7-07
INV. NO. 2008060712

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 01 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

HO.

Signed

Case Morris

(TECHNICIAN)


Form CP-2/3

PKP

OCT 15 2007

STATE KANS COUNTY RUSSELL
FIELD GORHAM (MULTIPAY)
OPER BARTON OIL
WELL 1 DUMLER "B"
API 15-167-01688-0001
SPUD 11/03/1980
DTD 3302 LTD FTD ARBUCKLE

OWWO RE-ISSUE
WELL CLASS DO
STATUS OIL-WO
COMP 09/28/1981
PBD

1-14S-15W
C SW SE
660FSL 1980FEL SEC


LOC Petroleum Information Corporation

IP IPP 2 BOPD 20 BW EL: 1871 KB
PROD ZONE: TOPEKA 2756-2760

OWWO: OLD INFO: FORMERLY TEXAS CO 1-B DUMBLER. SPUD 7/30/42. 10 3/4 @ 249
W/CMT, 5 1/2 @ 3298 W/CMT. SPL TOPS: LANSING-3026, GORHAM 3295.
OTD 3302. COMP 9/30/42. IPP 4 BOPD + 54 BWP. PROD ZONE NOT RPTD.

NEW:
PERFS: TOPEKA PERF 2756-2760
ACID 2000 GALS 28%
NO CORES OR DSTS

Plugged in 1957

OPER ADDRESS: BOX 589, RUSSELL, KS 67665
CONTR: ZIGLER SERVICES
ID CHANGES: SPOT CHGD FROM NE SW SE

REISSUE TO: CORRECT SPOT, SPUD & COMP DATES, CSG DEPTH ON OLD INFO
ADD FTG
REPLACEMENT FOR CARD ISSUED 10/13/81

KS R2-091890

Copyright 1990 Petroleum Information Corporation