

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02911-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 17-9S-21W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: COOLEY B Well #: 4
County: GRAHAM Total Vertical Depth: 3780 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|---------------|
| PROD | 5.5 | 3772 | 0 | w/75 sxs cmt |
| SURF | 8.625 | 175 | 0 | w/125 sxs cmt |

122.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2007 9:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 14 sxs gel - 800# hulls.
CIBP at 3740'. PBTB 3395'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2007 1:40 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3360' - pumped 60 sxs cement with 300# hulls.
Pulled tubing to 2780' - pumped 15 sxs gel with 100# hulls in the last 5 sxs.
Pulled tubing to 1095' - pumped 80 sxs cement with 200# hulls - good circulation of cement.
Pulled tubing out - tied onto 5 1/2" casing - squeezed with 10 sxs cement to Max. P.S.I. 300#.
Tied onto backside - squeezed with 90 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3518 | 3669 | | |

INVOICED

DATE 11-7-07
INV. NO. 2008060714

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 02 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #24730.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

Form CP-2/3

PKT

OCT 31 2007

PALMER OIL & NAT COOP #1 COOLEY B 17-9-21W
 SW SW NE


Contr. PALMER OIL CORPORATION GRAHAM County

E 2274 Comm Comp. 5-26-50 IP 3000 BOPD

| Tops | Depth | Datum | Casing |
|------|-------|-------|---------|
| ANH | 1755 | +519 | 8" 175 |
| LKC | 3468 | -1194 | 5" 3772 |
| | | | |
| | | | |
| | | | |
| ARB | 3770 | -1496 | |
| I.D. | 3780 | -1506 | |

1500' OIH/3 HRS:
 ACID 1000

MOREL POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS