

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05961-00-00
Spot: NWSENE Sec/Twnshp/Rge: 28-11S-17W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: BEMIS SHUTTS A Well #: 12
County: ELLIS Total Vertical Depth: 3543 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD Bowman oil co.
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	16	30		
PROD	7	3516	0	w/200 sxs cmt
SURF	10.75	1213	0	w/450 sxs cmt

115.15

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2007 11:45 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 885-4830

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 1000# hulls.
PBTD 3502'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2007 6:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfed at 1800' - 1225' - 675'.
RIH with tubing to 2918'. Rigged to tubing - pumped 40 sxs cement with 150# hulls mixed in.
Pulled tubing to 2750'. Rigged to tubing - pumped 10 sxs gel with 150# hulls mixed in, followed with 5 sxs cement.
Pulled to 2438' - pumped 5 sxs gel, followed with 10 sxs cement.
Pulled tubing to 1825'. Rigged to tubing - pumped 6 sxs gel, followed with 30 sxs 60/40 pozmix and displaced to 1250'.
Pulled tubing to 1250'. Rigged to tubing - pumped 375 sxs cement wit 700# hulls mixed in. Ran out of cement. Ordered an additional 150 sxs.
Pulled tubing to 625'. Backside 10 3/4" and 16" was orange peeled and welded together - good circulation out of 7" and backside.
Rigged to tubing at 625' - pumped 100 sxs to circulate cement up backside and 7" casing.
Pulled tubing - rigged to 7" casing with a swedge and pumped 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3253	3257		

INVOICED
DATE 11-7-07
INV. NO. 2008060715

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 01 2007

Remarks: ALLIED CEMENTING COMPANY-TICKET #24778.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

prep

THE TEXAS CO

#A-12 BEMIS

28-11-17W
NW SE NE

Contr.

ELLIS County

E. 1995

Comm. 8-20-37

Comp. 10-17-37


IP

788 BOPD

Tops	Depth	Datum
ARB	3516	
TD	3513	

Casing
7" 3516

Fay 3516: A/5000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS