

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21465-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 4-29S-15W
1918 feet from S Section Line, 4920 feet from E Section Line
Lease Name: BOLSER Well #: 1
County: PRATT Total Vertical Depth: 4820 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4640		WITH 2 SX CMT
PROD	5.5	4819	2800	WITH 200 SX CMT
SURF	8.625	429		WITH 250 SX CMT

156.65

Well Type: EOR UIC Docket No: E27999.3 Date/Time to Plug: 10/12/2007 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (316) 262-1077

Proposed Plugging Method: CIBP @ 4640' & 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2007 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4640' & PUT 2 SX CMT ON TOP OF PLUG THROUGH DUMP BAILER. LAY DOWN CASING AND RUN 2 3/8" TUBING TO PLUG THROUGH. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4698	4712		

INVOICED
DATE 11-7-07
INV. NO 2008060722


RECEIVED
KANSAS CORPORATION COMMISSION
NOV 01 2007

Remarks: USED 60/40 POZMIX 4% GLE BY ALLIED.

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed Stephen J. Pfeifer
(TECHNICIAN)