

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22224-00-00
Spot: NESWNW Sec/Twnshp/Rge: 32-12S-17W
1650 feet from N Section Line, 990 feet from W Section Line
Lease Name: GIEBLER Well #: 1
County: ELLIS Total Vertical Depth: 3703 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE STE 740 LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3700	0	w/125 sxs cmt
SURF	8.62	238	0	w/150 sxs cmt

120.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2007 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: FRANCIS J. GIEBLER Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2628

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2007 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfed at 1850' - 1308' - 773' - 288'.
Ran tubing to 3000' - pumped 50 sxs 60/40 pozmix - 4% gel cement with 500# hulls.
Pulled to 2500' - pumped 13 sxs gel.
Pulled to 1850' - circulated with 145 sxs cement with 300# hulls.
POOH. Tied onto casing and pumped 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Pressured backside to 500# P.S.I.

Perfs:

INVOICED
DATE 11-7-07
INV. NO. 2008060723

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 02 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed *Case Morris*
(TECHNICIAN)

100

OCT 31 2007

PRP

GIEBLER BROS.
 53 S. KANSAS ST.
 RUSSELL, KS 67665

#1 GIEBLER

32-12-17W
 NE SW NW

CONTR BUFFALO DRILLING CO. CTY ELLIS

GEOL _____ FIELD SCHMEIDLER

E 2079 KGCM 2/12/81 CARD ISSUED 5/14/81 IP P 110 80 & 75 BWPD
2073 GL ARB 3616-19 &
3655-59

API 15-051-22,224

LOG	TOPS	DEPTH	DATUM
TOP		3063	- 984
HEEB		3300	-1221
TOR		3322	-1243
LKC		3348	-1269
CONG		3607	-1528
ARB		3615	-1536
RTO		3703	-1624

8-5/8" 238/15J_{sx}, 5 1/2" 3708/125_{sx}
 DST (1) 3616-3622 (ARB)/30-60-30-60,
 REC 1500' O, 362' W, SIP 895-
 860#, FP NA
 MICT - CO, PF (ARB) 3655-59, AC
 250 G (MCA), SWB LD W/TR O, AC 500
 G (15%), SWB LD & SWB 10 BOPH, AC
 1500 G (15%), SWB 28 BOPH, NW, PF
 (ARB) 3628-30, ISOLATE ZN, TST
 ALL WTR, PF (ARB) 3616-19, AC 250
 G (MCA), SWB LD W/TR O, AC 500 G
 (15%), SWB LD & SWB 15 BOPH, AC
 1500 G, SWB 41 BOPH, NW, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS