

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24066-00-01
Spot: E2SWNW Sec/Twnshp/Rge: 32-12S-17W
3358 feet from S Section Line, 4428 feet from E Section Line
Lease Name: GIEBLER A Well #: 5
County: ELLIS Total Vertical Depth: 3707 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE STE 740 LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3699	0	125 SX CMT
SURF	8.625	264	0	160 SX CMT

120.48

Well Type: SWD UIC Docket No: D25258.0 Date/Time to Plug: 10/19/2007 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: FRANCIS J. GIEBLER Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2628

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2007 10:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 50 sxs 60/40 pozmix - 4% gel cement with 500# hulls, followed with 14 sxs gel, followed with 190 sxs cement.
Max. P.S.I. 800#. S.I.P. 50#. Backside full of cement.

Perfs:

INVOICED
DATE 11-7-07
INV. NO. 2008060723

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 02 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

District: 04

10

Signed Case Morris
(TECHNICIAN)

OCT 31 2007

PKP

GIEBLER OIL, INC.

53 S. KANSAS

RUSSELL, KS 67665

CONTR. SHIELDS DRILLING CO.

GEOLOGIST DAVID SHUMAKER

ELV 2073 KB SPD 10/29/84

2068 GL

CARD ISSUED 3/14/85

P 5 BOPD & WTR

ARB 3613-3618


#5 GIEBLER

CTY ELLIS

FIELD SCHMEIDLER

32-12-17W

C. E/2 SW NW



LOG	Type	Depth/Datum	API 15-051-24,066
ANH		1297 + 776	8 5/8 " 264 / 160SX, 5 1/2 " 3699 / 450SX NO CORES OR DSTS MICT - CO, PF (ARB) 20 / 3613-18, AC 250G (15% MA), SWB LD, SO, RE-AC 1000G (15% INS), SWB DWN, SO, POP, P 5 BOPD & WTR
B/ANH		1332 + 741	
TOP		3055 - 982	
HEEB		3292-1219	
TOR		3313-1240	
LANS		3340-1267	
BKC		3573-1500	
CONG		3602-1529	
ARB		3606-1533	
RTD		3700-1627	

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS