

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24361-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 6-20S-23W  
2180 feet from N Section Line, 1730 feet from W Section Line  
Lease Name: CUNNINGHAM CJ Well #: 1-6  
County: NESS Total Vertical Depth: 4424 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1620		WITH 155 SX CMT
PROD	5.5	4419	0	WITH 200 SX CMT
SURF	8.625	215		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2007 3:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC. **143.78**  
Proposed Rcvd. from: MIKE FRITZLER Company: PINTAIL PETROLEUM Phone: (316) 263-2243

Proposed Plugging Method: PUMP 50 SX CMT WITH GEL SPACER TO ANHYDRITE THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/16/2007 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 50 SX CMT WITH 200# HULLS MIXED IN, 19 SX GEL, 150 SX CMT. MAXIMUM PRESSURE 850#. ON SLIGHT VACUUM. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 30 SX CMT. PRESSURED TO 500# & HELD. 10/17/07: TOPPED OFF WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4404	4410		
4398	4402		

**INVOICED**  
DATE 11-9-07  
INV. NO. 2008060746

RECEIVED  
KANSAS CORPORATION COMMISSION  
**NOV 05 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED  
OCT 26 2007  
KCC Dodge City

Signed Michael J. Maier  
(TECHNICIAN)