

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21760-00-00
Spot: SESESW Sec/Twnshp/Rge: 12-20S-6W
526 feet from S Section Line, 3038 feet from E Section Line
Lease Name: MURRAY Well #: 1
County: RICE Total Vertical Depth: 3370 feet

Operator License No.: 30979 •
Op Name: NIGHTINGALE, RUSSELL DBA R J OPE
Address: 1044 24TH AVE
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3367		150 SX
SURF	8.625	206		175 SX

109.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2007 11:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYR Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/19/2007 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND TO 3200' AND CAP WITH 5 SX'S CEMENT CUT OFF CASING AT 2450' AND PULL TO 850' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 450' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 260' AND CIRCULATE CEMENT TO SURFACE.

INVOICED

DATE 11-9-07
INV. NO. 2008060748

Perfs:

Remarks: 60-40 POZ, 4% GEL. QUALITY TICKET #1494

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 05 2007
CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKT