

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Becker Oil Corporation
Address: P. O. Box 1150, Ponca City, OK 74602
Phone: (303) 816-2013 Operator License #: 31093
Type of Well: J&A LH KCCPKT per CP2/3 Docket #: CP2/3
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 13, 2007 (Date)
by: Dodge City office (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet):

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 081-21758-00-00
Lease Name: Bedell
Well Number: A-4
Spot Location (QQQQ): _____ - _____ - SW - NE
1881 Feet from North / South Section Line
1842 Feet from East / West Section Line
Sec. 9 Twp. 27 S. R. 31 East West
County: Haskell
Date Well Completed: 10/15/07
Plugging Commenced: 10/14/05
Plugging Completed: 10/15/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	1787	8 5/8"	43 jts	0
RECEIVED KANSAS CORPORATION COMMISSION FEB 22 2008						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method of introduction used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 75 sx 13.5# ASC, 25 gel, 5% GL-160 at 5025' across Morrow sand, set plug to sidetrack into new hole with 100 sx common, 3% cc. Waited on cement. Plugged with 50 sx at 1790', 50 sx at 880', 20 sx at 60', 60/40 poz, 6% gel, 1/4# Flo-seal. Plug down

Name of Plugging Contractor: Trinidad Drilling Limited Partnership License #: 33784
Address: P. O. Box 31, Russell, KS 67665


Name of Party Responsible for Plugging Fees: Becker Oil Corporation
State of Colorado County, Jefferson, ss.
Clyde M. Becker, Jr.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Clyde M Becker Jr
(Address) P. O. Box 1550, Conifer, CO 80433

SUBSCRIBED and SWORN TO before me this _____ day of January, 20 08

Carmella L Miller My Commission Expires: 1/25/10
Notary Public



PKT