

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: ENHR Docket #: E-28-031
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD of ENHR)
The plugging proposal was approved on: 2-26-08 (Date)
by: Jack Macliskey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 4076 Bottom: 4278 T.D. 5355
Morrow Depth to Top: 5078 Bottom: 5128 T.D. 5355
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-081-21287-00-02
Lease Name: Frey Morrow Unit
Well Number: 103 W
Spot Location (QQQQ): NE-SW-SE
1259 Feet from North / South Section Line
1847 Feet from East / West Section Line
Sec. 13 Twp. 27 S. R. 34 East West
County: Haskell
Date Well Completed: 2-25-2000 spud
Plugging Commenced: 2-27-08
Plugging Completed: 2-29-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1783	—
				5 1/2	5355	2171

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2008
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 100 lb. hulls & 25 sx plug thru 2 3/8 above lower perms from 5078 to 4878. Pull 2 3/8 to 3876, mixed 400 lb. hulls & 25 sx plug from 3876 to 3676. Circ 5 1/2 w/mud. Pull 5 1/2 to 1810. Circ. hole w/mud & mix 50 sx plug 1810 to 1660 40 sx 830 to 710 10 sx 40 to 0 Capped 8 5/8 8 ft below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc 1701 N. Kansas PO Box 2528 Liberal, KS, 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenny Andrews
(Address) 1701 N. Kansas PO Box 2528 Liberal, KS 67905

SUBSCRIBED and SWORN TO before me this 24 day of March, 2008
Anita Peterson My Commission Expires: Oct. 1, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 1, 2009